



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite, Philippines
(046) 415-0010
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL / BID BULLETIN - 1

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of Old College Library Building (For GAD Office)** with an **ABC of ₱ 1,768,483.06**.

1. Site inspection is a must. An additional sheet for electrical post is provided.
2. On concrete/masonry/tile works:
 - a. All existing comfort rooms must be repaired and be subjected to tile removal and replacement.
 - b. A new comfort room and a lactation room shall be installed.
 - b.1. CHB partitions should be provided.
 - b.2. Tiles shall be provided for these new rooms @ grid I-J/1-1'.
 - c. Provide granite tiles for the concrete counter.
 - d. Replastering works for the surrounding canopy and interior slab shall be provided.
3. On carpentry and miscellaneous works:
 - a.1. Remove the existing partition with care. They are to be reinstalled @ grids B & F-J.
 - a.2. Existing doors shall be removed with care for reinstallation to the stock room. Provide repairs and door accessories as necessary.
 - a.3. All D2 shall be 0.80m x 2.10 m while D3 shall be 0.90m x 2.10m
 - a.4. Door on the stairwell shall remain and so with perimeter doors @ grid J and grid 1.
 - a.5. As all existing windows shall be repaired, include the provision of aircon casing.
4. On plumbing works:
 - a.1. Remove and replace all existing water supply and sewer lines for all existing comfort rooms including the upper floor.
 - a.2. Installation of new water supply line using PPR pipes and fittings. Tap to the source.
 - Provide a gate valve for each comfort room and one main gate valve from the source.
 - Provide heavy duty faucet for each cubicle
 - a.3. Installation of new sewer line system using PVC orange pipe and fittings.
 - Provide two units brass floor drains for each comfort room to be connected to the existing canal. Provide restoration works for the existing canal adjacent to grid 3.
 - The new CR @ grid I-J shall be tapped to the existing septic tank on the west side of the GAD office.
 - a.4. For plumbing fixtures:
 - All fixtures must be colored and complete with all heavy duty fittings and accessories.
5. On electrical works:
 - a.1. Remove and replace all existing electrical lines. See plan for the installation of new electrical lines. Tapping is at most 60 meters from building to source.
6. For painting: Use **plant mixed semi-gloss dirt resisting latex paint** for final coating.
7. This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and be included in the financial envelop.

8. The Construction and Safety Health Program of the Contractor to be submitted in this bidding procedure must be certified by its President/Owner. DOLE approved CSHP may be required upon post qualification.
9. All projects to be undertaken by a contractor of the university should have its own electrical and resident site engineers.

For guidance and information of all concerned.

Prepared by:

(SGD) MICHELLE A. SANTOS

BAC Secretary

Approved by:

(SGD) CAMILO A. POLINGA, PhD

Chair, BAC for Infrastructure Projects

Received by the Bidder : _____

Date : _____