



**CAVITE STATE UNIVERSITY**  
**Don Severino de las Alas Campus**

Indang, Cavite, Philippines

☎ (046) 415-0010 / 📠 (046) 4150-0013 loc 203

www.cvsu.edu.ph

**REQUEST FOR QUOTATION**

**Improvement of Cavite City Campus – Construction of Storm Drainage**

1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project **“Improvement of Cavite City Campus – Construction of Storm Drainage”** with an Approved Budget for the Contract (ABC) of **Six Hundred Thirty-Five thousand Two Hundred Nineteen Pesos and 9/100 Only (PhP 635,219.09)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.			Improvement of Cavite City Campus – Construction of Storm Drainage		635,219.09
<b>TOTAL AMOUNT</b>					<b>635,219.09</b>

2. The quotation must be submitted to the Supply Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of February 11, 2020**.

Address : Supply Office, Administration Building  
Cavite State University  
Indang, Cavite  
E-mail : supplyoffice@cvsu.edu.ph  
Telefax : (046) 862-0852

3. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.

  
**MICHELLE A. SANTOS**  
BAC Secretary, Infrastructure Projects



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino delas Alas Campus  
 Indang, Cavite

**BILL OF QUANTITIES**

<b>NAME OF PROJECT: IMPROVEMENT OF CAVITE CITY CAMPUS</b> – Construction of Storm Drainage ABC: ₱ 635,219.09 COLLEGE/UNIT/CAMPUS: CvSU – IMUS CAMPUS					
				<b>Bill of Quantities</b>	
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	<b>EARTHWORKS</b> (Pesos _____ _____ and _____ centavos)				
II	<b>CONCRETE AND MASONRY WORKS</b> (Pesos _____ _____ and _____ centavos)				
III	<b>MISCELLANEOUS WORKS</b> (Pesos _____ _____ and _____ centavos)				
<b>GRAND TOTAL</b>					_____
<b>Write grand total in words</b>		_____ _____ _____			

Submitted by: \_\_\_\_\_ Date: \_\_\_\_\_  
 Name of Bidder/Bidder's Representative: \_\_\_\_\_  
 Position: \_\_\_\_\_  
 Construction Company/Contractor: \_\_\_\_\_

**A. IMPROVEMENT OF CAVITE CITY CAMPUS – Construction of Storm Drainage**

1. The project must be finished in 90 working days.
2. Actual site inspection is a must.

**B. TECHNICAL DESCRIPTION**

**I. Earthworks**

- a. Dismantling, Excavation and Hauling
  1. This work includes excavation for storm drainage.
  2. The area should be cleared before and after the construction work.

**II. Concrete and Masonry Works**

- a. Provide concrete open canal with 16mm RSB grills.
- b. Supply and installation of RCP 24" from university fence to existing public storm drainage.
- c. Provide 2% slope of canal.
- d. Concreting of the affected concrete walk/pavement due to excavation of storm drainage.
- e. Concrete and masonry works should be plain cement finished.
- f. Provide necessary tools and equipment for the construction work.

**III. Miscellaneous Works**

- a. Supply and installation of 16mm RSB space @ 2" with ¼" x 2" angle bar grills.
- b. Provide epoxy primer with catalyst for the whole steel grills.

**IV. See plans and existing for details and extent of work.**