



**CAVITE STATE UNIVERSITY**  
**Don Severino de las Alas Campus**

Indang, Cavite, Philippines

☎ (046) 415-0010 / 📠 (046) 4150-0013 loc 203

www.cvsu.edu.ph

**REQUEST FOR QUOTATION**

**Labor for Repainting of Elevated Water Tank near Tennis Court**


1. The Cavite State University (CvSU) invites interested firms/suppliers to submit quotation for the project "**Labor for Repainting of Elevated Water Tank near Tennis Court**" with an Approved Budget for the Contract (ABC) of **Seventy Eight Thousand Three Hundred Eighty-Five Pesos and 74/100 Pesos Only (PhP 78,385.74)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

| Item No.            | Quantity | Unit | Description   | Unit Cost | Total Cost       |
|---------------------|----------|------|---|-----------|------------------|
| 1.                  |          |      | Labor for Repainting of Elevated Water Tank near Tennis Court |           | 78,385.74        |
| <b>TOTAL AMOUNT</b> |          |      |   |           | <b>78,385.74</b> |

2. The quotation must be submitted to the Supply Office through mail, fax or email at the contact details listed below on or before **5:00 PM of February 11, 2020**.

Address : Supply Office, Administration Building  
Cavite State University  
Indang, Cavite  
E-mail : supplyoffice@cvsu.edu.ph  
Telefax : (046) 862-0852

3. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.

  
**PRECIOSA G. ERAÑA**  
BAC Secretary, Goods and Services



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino delas Alas Campus  
 Indang, Cavite

**BILL OF QUANTITIES**

| <b>NAME OF PROJECT: LABOR FOR REPAINTING OF ELEVATED WATER TANK NEAR TENNIS COURT</b><br><b>ABC: ₱ 78,385.71</b><br><b>COLLEGE/UNIT/CAMPUS: ODA, CvSU INDANG CAMPUS</b> |   |      |          | <b>Bill of Quantities</b> |                         |
|---|---|------|----------|---------------------------|-------------------------|
| Item No.  | Description   | Unit | Quantity | Unit Price (Pesos)        | Amount (Pesos)          |
| I   | <b>SITE CLEARING AND PREPARATION</b><br>(Pesos _____<br>_____<br>and _____ centavos)    |      |          |                           |                         |
| II  | <b>PAINTING AND MISCELLANEOUS WORKS</b><br>(Pesos _____<br>_____<br>and _____ centavos) |      |          |                           |                         |
| <b>GRAND TOTAL</b>  |   |      |          |                           | _____                   |
| <b>Write grand total in words</b>   |   |      |          |                           | _____<br>_____<br>_____ |

Submitted by: \_\_\_\_\_ Date: \_\_\_\_\_  
 Name of Bidder/Bidder's Representative: \_\_\_\_\_  
 Position: \_\_\_\_\_  
 Construction Company/Contractor: \_\_\_\_\_

**A. LABOR FOR REPAINTING OF ELEVATED WATER TANK NEAR TENNIS COURT**

1. The project must be finished in 25 working days.
2. Actual site inspection is a must.
3. The area should be cleared before and after the construction work at least twelve meters away from the job site. Unusable formworks, excessive soil fill and all other unwanted debris of installation works should be disposed properly.

## **B. TECHNICAL DESCRIPTION**

### **I. Site Clearing and Preparation**

- a. Wire brush or scrape rusted materials. Let it stay for 10-18 minutes. Be sure to wash off surface thoroughly with water, letting it dry before applying paint. Prime immediately after drying.
- b. This work will include the structural frame and stainless body of the elevated water pump.

### **II. Painting and Miscellaneous Works**

#### **a. Painting Schedule and Application**

##### **1. Roof**

##### **1.1. First and Second Coat**

- Epoxy primer with catalyst, gray
- Site clearing and hauling of debris is a must prior to completion of works.

### **III. Note**

- a. See/consult end-user for details/extent of work. The silence of specification, plans, special provision and supplementary specifications as to any detail, or the apparent omission therein of a detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.
- b. All works will be facilitated by the contractor.
- c. All tools and equipment necessary for executing the work will be provided by the contractor/PPS Office.
- d. Works that are necessary but are not cited in the above specifications will be facilitated by the PPS.
- e. Materials that are necessary but are not included in the above program of works will be provided by the contractor.
- f. No modifications will be done without the approval of end-user, project inspector, and implementor.
- g. Verify actual measurement on site.
- h. Scaffolding will be provided by PPS.