



CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus

Indang, Cavite, Philippines

☎ (046) 415-0010 / 📠 (046) 4150-0013 loc 203

www.cvsu.edu.ph

REQUEST FOR QUOTATION

Labor for Repainting of Roofing of Administration Building

1. The Cavite State University (CvSU) invites interested firms/suppliers to submit quotation for the project "**Labor for Repainting of Roofing of Administration Building**" with an Approved Budget for the Contract (ABC) of **Ninety-Two Thousand Two Hundred Eighty-Nine Pesos and 92/100 Only (PhP 92,289.92)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.			Labor for Repainting of Roofing of Administration Building		92,289.92
TOTAL AMOUNT					92,289.92

2. The quotation must be submitted to the Supply Office through mail, fax or email at the contact details listed below on or before **5:00 PM of February 13, 2020**.

Address : Supply Office, Administration Building
Cavite State University
Indang, Cavite
E-mail : supplyoffice@cvsu.edu.ph
Telefax : (046) 862-0852

3. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


PRECIOSA G. ERAÑA
BAC Secretary, Goods and Services



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

NAME OF PROJECT: LABOR FOR REPAINTING OF ROOFING OF ADMINISTRATION BUILDING ABC: ₱ 92,289.92 COLLEGE/UNIT/CAMPUS: CvSU INDANG CAMPUS					
					Bill of Quantities
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	SITE CLEARING AND PREPARATION (Pesos _____ _____ and _____ centavos)				
II	ROOFING AND PAINTING WORKS (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words		_____ _____ _____			

Submitted by: _____ Date: _____
 Name of Bidder/Bidder's Representative: _____
 Position: _____
 Construction Company/Contractor: _____

A. REPAINTING OF ADMINISTRATION BUILDING (EXTERIOR)

1. The project must be finished in 60 working days.
2. Actual site inspection is a must.
3. The area should be cleared before and after the construction work at least twelve meters away from the job site. Unusable formworks, excessive soil fill and all other unwanted debris of demolition works should be disposed properly.

B. TECHNICAL DESCRIPTION

I. Site Clearing and Preparation

- a. Removal of Old Valley Gutter
 1. This work will include all valley gutter at the roofing of Administration Building.
- b. Surface Preparation for Repainting of Roofing
 1. Wire brush or scrape rusted materials. Let it stay for 10-15 minutes. Be sure to wash off surface thoroughly with water, letting it dry before applying paint. Prime immediately after drying.

II. Roofing and Painting Works

- a. Roofing Works
 1. Installation of new stainless valley gutter.
 2. All roofing nails and screws must be waterproofed with sealant.
- b. Painting Schedule and Application
 1. First Coat
 - 1.1. One coat of red oxide primer.
 2. Top Coat
 - 2.1. Two coats of gloss-acrylic water based roofing paint, baguio green.
 - 2.2. Cleaning of gutter is included.

III. Note

- a. See/consult end-user for details/extent of work. The silence of specification, plans, special provision and supplementary specifications as to any detail, or the apparent omission therein of a detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.
- b. All works will be facilitated by the contractor.
- c. All tools and equipment necessary for executing the work will be provided by the contractor/PPS Office.
- d. Works that are necessary but are not cited in the above specifications will be facilitated by the PPS Office.
- e. Materials that are necessary but are not included in the above program of works will be provided by the end user.
- f. No modifications will be done without the approval of end-user, project inspector, and implementor.
- g. Verify actual measurement on site.
- h. Scaffoldings will be provided by PPS.