



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
☎ (046) 4150-010/4150-011
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL / BID BULLETIN - 1

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of Piggery – 2nd Posting** with an **ABC of ₱ 1,612,226.87**.

1. Site inspection is a must.
2. Concrete and Masonry works:
 - a. All existing and new concrete and masonry works should be plastered plain cement finished.
3. Carpentry works
 - a. Supply and installation of fiber cement board for ceiling with 1.2mm thick metal furring for ceiling joist. (1" x 2" furring, wall angle, channel and all other accessories spaced @ 0.40 m on center bothways).
4. Trusses and Roofing including all other steel works
 - a. Instead of 3" Ø as planned, use 4" Ø GI pipe S-40 for post to be embedded in the pedestal column.
 - b. Roofing sheets should be ga. 26 (0.5 mm).
5. Electrical works
 - a. All bulbs must be installed with 4" PVC receptacle.
6. Painting works should be semi-gloss finished. Consult end user for color preference.
7. This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and be included in the financial envelop.
8. The Construction and Safety Health Program of the Contractor to be submitted in this bidding procedure must be certified by its President/Owner. DOLE approved CSHP may be required upon post qualification.
9. All projects to be undertaken by a contractor of the university should have its own electrical and resident site engineers.

Prepared by:


MICHELLE A. SANTOS
BAC Secretary

Approved:


MA. AGNES P. NUESTRO, PhD
Chair BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____