



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite, Philippines
(046) 415-0010
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL / BID BULLETIN NO. 2

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of CAFENR Agricultural Science Building** with an **ABC of ₱ 1,047,361.70**.


1. Site inspection is a must. See actual site for verification of sizes and location.
2. Include mobilization cost as an item 2 under dismantling/chipping works.
3. On carpentry works:
 - a. Framing and posts of long tables must be 2" x 3" KD lumber with 1" x 4" KD perimeter bracing.
4. On miscellaneous works:
 - a. Fabrication and supply of two units stainless ladder from second to ground floor.
- use 1/4" x 2" stainless flat bar with 2.0 mm thick stainless tubing.
 - b. The gutter to be plastered and waterproofed is the entire outermost front of the building.
5. On plumbing works:
 - a. Remove and replace the existing sewer lines including the fittings of the fixtures.
6. On electrical works:
 - a. All existing lighting fixtures should be reinstalled to the newly installed ceiling.
 - b. Adjustment on wires should be provided for lighting fixtures re-installation on the ceiling.
7. On painting works:
 - a. All newly installed ceiling works should be painted.
 - b. The undersides of slab, the metal decking, should be primed and painted.
8. This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.
9. The Construction and Safety Health Program of the Contractor to be submitted in this bidding procedure must be certified by its President/Owner. DOLE approved CSHP may be required upon post qualification.
10. All projects to be undertaken by a contractor of the university should have its own resident site engineers. Also, it is required that an electrical engineer or a master electrician be a part of contractors team to supervise all electrical works.

General Notes:

1. The Statement of the Bidder's Single Largest Completed Contract (SLCC) shall be supported by the Notice of Award and/or Notice to Proceed, Project's Certificate of Final Acceptance.
2. The Statement of the Bidder's Ongoing and Completed Government and Private Contracts must contain a complete list of all the bidder's ongoing and completed contracts both with government and private entities.
3. For Implementation Health Protocols, DPWH Department Order No. 35, Series of 2020, Construction Safety Guidelines for the Implementation of All DPWH Infrastructure Projects During the COVID-19 Public Health Crisis shall be applied. *(See attached copy of DPWH DO No. 35, s. 2020)*


For guidance and information of all concerned.

Prepared by:


EFREN R. ROCILLO
Chair, TWG


CENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member


ELIPIDIO N. RODEROS, JR.
TWG Member


RONALD P. PEÑA
TWG Member


MICHELLE A. SANTOS
BAC Secretary

Approved by:

(SGD) MA. AGNES P. NUESTRO, PhD
Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____