



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 2**


This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Rehabilitation of Comfort Rooms at CvSU Carmona Campus (CvSU-BAC-INFRA-21-011)** with an ABC of ₱ 1,225,267.84:

1. Site inspection is a must. All comfort rooms on the North Wing of the building shall be subjected to rehabilitation.  
*\*There are sheets additional plan: schedule of doors, electrical layouts for all floors and septic tank.*
2. On earthworks:
  - a. Mobilization cost is to be included under earthworks
  - b. Removal of all existing old tiles including partitions of comfort rooms from ground to third floors
  - c. Removal of all existing floor tiles at fourth floor.
3. On concrete, masonry and tile works:
  - a. Lavatory counters must be 4" thick reinforced with 10 mm 0 deformed bars spaced at 0.15 meters on center both ways. It must be supported with CHB walls at a maximum of 2.0 meters span. Sloped counters is to be used.
  - b. Supply and installation of ceramic locally made colored tiles for the comfort rooms.
    - b.1 12" x 12" unglazed floor tiles (ground to fourth floor) including slop sink.
    - b.2 12" x 12" glazed wall tiles (ground to third floor)
  - c. Retouching/minor improvement works to fit the new works to the existing shall be done.
4. On plumbing works:
  - a. Removal and replacement of all water supply, sewer line and fixtures from ground to third floors.
  - b. Removal and replacement of all water supply and sewer line at fourth floor.
  - c. Provide at least 2 units brass counter drains for sloped lavatories.
  - d. Adopt S-1000 PVC orange pipes and fittings. For VSTR, 4" 0 shall be used.
  - e. Apply waterproofing on all comfort rooms.
5. On electrical works:
  - a. Repair and improvement of all electrical system affected by the new lay-out of the comfort rooms.
  - b. Provide switches and outlets for the comfort rooms including the hallway.
6. On painting works:
  - a. Painting and repainting of all comfort rooms including ceiling, doors and windows.
7. On painting works:
  - a. Painting and repainting of all comfort rooms including ceiling, doors and windows.
8. In case of expired PhilGEPS License, the following legal documents must be included in the bid to be submitted:
  - a. Registration certificate from Securities and Exchange Commission (SEC), Department of Trade and Industry (DTI) for sole proprietorship, or Cooperative Development Authority (CDA) for cooperatives or its equivalent document; and
  - b. Mayor's or Business permit issued by the city or municipality where the principal place of business of the prospective bidder is located, or the equivalent document for Exclusive Economic Zones or Areas; and
  - c. Tax Clearance per E.O. No. 398, s. 2005, as finally reviewed and approved by the Bureau of Internal Revenue (BIR).
9. This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.
10. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works.

For guidance and information of all concerned.


Prepared by:

  
**EFREN R. ROCILLO**  
TWG Chair


  
**CENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member

  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

Approved by:

  
**MA. AGNES P. NUESTRO, PhD**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_