



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 1**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of Two Units Goat House (CvSU-BAC-INFRA-21-014)** with an **ABC** of **₱ 1,207,770.57**:

1. Site inspection is a must. Verify actual condition of site.
2. On trusses and roofing:
  - a. Use 2" x 4" channel bars for top and bottom chords; and 2" x 3" channel bar for web members. Entire truss system shall be painted.  
Note:  
\* Apply two coats epoxy primer finished with at least two coats quick dry enamel paint.
  - b. GI pipes S-40 1 1/2" Ø and 1" Ø shall be used for lateral frame around the building.
  - c. Rib type roofing sheets, cladding and bended accessories shall be ga. 26 (0.50mm).
3. This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.
4. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works.

For guidance and information of all concerned.

Prepared by:

  
**EFREN R. ROCILLO**  
TWG Chair


  
**CENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member

  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

Approved by:

  
**MA. AGNES P. NUESTRO, PhD**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_