



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)


SUPPLEMENTAL / BID BULLETIN NO. 2

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of Coffee Processing (Replacement of Roofing & Installation of Tiles) (Cvsu-BAC-INFRA-22-016)** with an ABC of ₱ 2,709,138.78:


1. Site inspection is a must. Verify actual condition of site.
**Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
2. On dismantling works:
 - a. Removal of all roofing sheets for the entire area of the building. Removal of tiles of the comfort rooms. Chipping of ground slab to prepare for installation of tiles.
 - b. All dismantled materials should be piled and hauled to the designated place.
3. On masonry/tile works:
 - a. All walls and structures affected by the dismantling/repair works should be retouched/be plastered plain cement finish.
 - b. Installation of tiles for the whole untiled flooring of the building.
 - c. Installation of colored tiles to the entire walls and floors of the two comfort rooms.
4. On roofing works:
 - a. Supply and installation of gauge 26 (0.5 mm) rib type pre painted long span roofing sheets with 20 mm thick insulation (sandwiched panel type).
5. On electrical and plumbing works:
 - a. Supply and installation of all fixtures as listed in the original BOQ.
 - b. Check and supply additional wirings for the installation of electrical lighting.
 - c. Check the sewer and water supply lines prior to fixtures installation. Provide necessary adjustments/cleaning.
6. For colors/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
7. *This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.*
8. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works.
9. In cases of participation to two or more projects, the set of workers and foreman shall be different per project however, the set of engineers and equipment may be reused.


Prepared by:


EFREN R. ROCILLO
TWG Chair



CENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member


RONALD P. PEÑA
TWG Member


ELPIDIO N. RODEROS, JR.
TWG Member

Approved by:


ENGR. ORLANDO B. DELOS REYES
Vice Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____