



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)


SUPPLEMENTAL / BID BULLETIN NO. 2

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Improvement of University Library (Removal and Replacement of Floor Tiles at Ground Floor) (CvSU-BAC-INFRA-22-014)** with an ABC of **₱ 1,290,420.00**:


1. Site inspection is a must. Verify actual condition of site.
**Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
2. On dismantling works:
 - a. Removal of all floor tiles at ground floor.
 - b. All dismantled materials should be piled and hauled to the designated place.
3. On masonry/tile works:
 - a. Supply and installation of tiles for the entire flooring of ground floor. See attached plan. (All grids except elevator, electrical and plumbing rooms, comfort rooms and stairs)
 - b. All affected areas including doors, flooring and walls affected by tile works should be retouched/plain cement finished.
4. For colors/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
5. *This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.*
6. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works.
7. In cases of participation to two or more projects, the set of workers and foreman shall be different per project however, the set of engineers and equipment may be reused.


Prepared by:


EFREN R. ROCILLO
TWG Chair



CENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member


RONALD P. PEÑA
TWG Member


ELPIDIO N. RODEROS, JR.
TWG Member

Approved by:


ENGR. ORLANDO B. DELOS REYES
Vice Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____