

Republic of the Philippines

CAVITE STATE UNIVERSITY

Don Severino delas Alas Campus Indang, Cavite

BILL OF QUANTITIES

INSTA	OVEMENT OF TRECE CAMPUS (SUPPLY LLATION OF TILES)	/ AND				
	ABC: ₱ 1,579,091.18 COLLEGE/UNIT/CAMPUS: TRECE CAMPUS			Bill of Quantities		
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)	
	TILE WORKS (Pesos					
I	and centavos)					
	GRAND TOTAL					
	Write grand total in words					
Submitted by: Name of Bidder/Bidder's Representative: Position:			Date:			
	tion Company/Contractor:					

CAVITE STATE UNIVERSITY

SCOPE OF WORK:

A. IMPROVEMENT OF TRECE CAMPUS (SUPPLY AND INSTALLATION OF TILES) GENERAL NOTES:

- 1. The project should be finished in 60 calendar days.
- 2. Actual site inspection is a must.

B. Technical Description

I. Tile Works

Supply and installation of the following:

- 1. Ceramic tiles (locally made) 0.40m. x 0.40m. for the whole area of lower and upper ground floor and second floor of the building. Unglazed ceramic tiles for hallways and walkways. Tiles must be accented with dark colors.
- 2. Granite tiles with groove for the steps and ceramic tiles for the riser of all stairs.
- 3. Tiles must be installed by using tile adhesive and finished with appropriate tile grout.
- 4. Consult the end-user for the color preference of tiles.
- C. See plans/consult the end-user and project inspector for details and extent of work. The silence of specifications, plans, special provisions and supplementary specifications as to any detail, or the apparent omission therein of detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.