



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)

SUPPLEMENTAL / BID BULLETIN NO. 1


This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Completion of HRM Hostel Building at Carmona Campus (CvSU-BAC-INFRA-22-023)** with an **ABC of ₱ 6,241,079.74:**

1. Site inspection is a must. There is an existing building. Verify actual condition of site.
**Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
2. On concrete/masonry/tile works:
 - a. Existing concrete and CHB walls should be plastered plain cement finish.
3. On carpentry/ceiling work:
 - a. Ceiling ventilation should be spandrel with holes.
 - b. Any commercially available decorative wood molding may be used.


Note: Choices on commercially available materials need the approval of inspector/end user.
4. On electrical works:
 - a. Provide 53 sets 2-18W LED flourescent lamp with diffuser.
 - b. Installation of one unit electrical meter.
 - c. Supply and installation of all special purpose outlets and ACU outlets.
5. On miscellaneous work:
 - a. Supply and installation of all doors and windows needed to complete the project.
- Include 2 sets D5 and 1 set W1
6. On plumbing works:
 - a. Installation of one unit water meter.
7. For colors/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end user sign your sample as proof of approval. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
8. *This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.*
9. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works. Likewise, master plumbers must supervise plumbing works.
10. In cases of participation to two or more projects, the set of workers and foreman shall be different per project however, the set of engineers and equipment may be reused.
11. Construction safety and health program and construction schedule (PERT/CPM/S-Curve) shall be provided by the winning bidder.


Prepared by:


EFREN R. ROCILLO
TWG Chair



CENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member


RONALD P. PEÑA
TWG Member


ELPIDIO N. RODEROS, JR.
TWG Member

Approved by:


ENGR. ORLANDO B. DELOS REYES
Vice Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____