



**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)


**SUPPLEMENTAL / BID BULLETIN NO. 1**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of Gymnasium (CvSU-BAC-INFRA-22-020)** with an **ABC** of **₱ 5,052,734.82**:


1. Site inspection is a must. Verify actual condition of site.
  - a. Provide retouching works to all parts of the building affected by the repair/improvement works.
  - b. Provide adjustments on doors that will be affected by tile works.
  - c. Provide a protective mat to cover the entire painted multi purpose court/playing area.
2. On concrete, masonry and tile works:
  - a. Supply and installation of colored locally made ceramic tiles 16" x 16" to the entire lower and upper floor of the building. Grids A to F/5 to 7 ; Grids A to F/1 to 2 ; Grids A to B/2 to 5 ; and Grids F to G/1 to 6, excluding bleachers.
3. On miscellaneous works:
  - a. Repair of existing W1 (the front window) by replacing all broken glasses and the accessories of awning aluminum casement windows.
  - b. Remove and replace the broken glasses of the main door. Replace hinges, handles and lock.
4. On plumbing works:
  - a. Removal and replacement of all systems (water supply, sewer and fixtures).
  - b. Supply and installation of one unit water meter.
  - c. Supply and installation of 10 sets shower head with valve and faucet.
5. For colors/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end user sign your sample as proof of approval.  
Note: In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
6. *This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.*
7. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works. Likewise, master plumbers must supervise plumbing works.
8. In cases of participation to two or more projects, the set of workers and foreman shall be different per project however, the set of engineers and equipment may be reused.
9. Construction safety and health program and construction schedule (PERT/CPM/S-Curve) shall be provided by the winning bidder.


Prepared by:

  
**EFREN R. ROCILLO**  
TWG Chair


  
**CENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member

  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

Approved by:

  
**ENGR. ORLANDO B. DE LOS REYES**  
Vice Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_