



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

| IMPROVEMENT OF BACoor CAMPUS (SUPPLY AND INSTALLATION OF STEEL DOORS) – 2nd POSTING ABC: ₱ 999,980.80 COLLEGE/UNIT/CAMPUS: BACoor CAMPUS | | | | | |
|--|---|------|----------|--------------------|---------------------------|
| | | | | | Bill of Quantities |
| Item No. | Description | Unit | Quantity | Unit Price (Pesos) | Amount (Pesos) |
| I | DISMANTLING WORKS (Pesos _____ _____ and _____ centavos) | | | | |
| II | MISCELLANEOUS WORKS (Pesos _____ _____ and _____ centavos) | | | | |
| III | MASONRY WORKS (Pesos _____ _____ and _____ centavos) | | | | |
| GRAND TOTAL | | | | | _____ |
| Write grand total in words | | | | | _____ _____ _____ |

Submitted by: _____ Date: _____
 Name of Bidder/Bidder's Representative: _____
 Position: _____
 Construction Company/Contractor: _____

CAVITE STATE UNIVERSITY

SCOPE OF WORK:

**A. IMPROVEMENT OF BACoor CAMPUS (SUPPLY AND INSTALLATION OF STEEL DOORS)
- 2nd POSTING**

GENERAL NOTES:

1. The project should be finished for 30 calendar days.
2. Site inspection is a must to verify site condition.
 - a. Site temporary enclosure may be blue sack or any suitable materials that may enclose the workplace.

B. Technical Description

I. Dismantling Works

1. Dismantling of existing doors (60 units)
2. All dismantled materials should be piled and hauled to the designated place.

II. Miscellaneous Works

1. Supply and installation of 60 sets of pre-painted steel flush door with ¼" thick clear glass view window complete with HD hinges and locksets. (1.0m X 2.10m)
2. All affected areas by the door installation should be retouched/ be plastered plain cement finish.

III. Masonry Works

1. Masonry works should be plastered plain cement.

C. For color/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end-user sign your sample as proof of approval. **Note: In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.**

D. See plans/consult the end-user and project inspector for details and extent of work. The silence of specifications, plans, special provisions and supplementary specifications as to any detail, or the apparent omission therein of detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.