



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)

BID BULLETIN NO. 1

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of Guest Rooms at Lower Ground Floor of International House 1 (CvSU-BAC-INFRA-22-036)** with an ABC of ₱ 3,096,109.63:

1. Site inspection is a must. Verify actual condition of site. There is an existing building.
 - a. The project should be completed as per plan and scope of work. A floor plan of IH1 is attached.
 - b. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
2. On site preparation: Removal and replacement of all doors, plumbing fixtures and lighting fixtures including switches, outlets and ACU outlets.
3. On carpentry works: Supply and installation of new doors to the room entrance and comfort rooms.
 - a. Panel steel door, 1.0 meter, pre-painted, complete with steel jamb, lever type heavy duty brass lockset and 4" LP hinges. (28 units)
 - b. Panel steel door with louver on the bottom part, 0.80 meter, pre-painted, complete with steel jamb, knob type heavy duty brass lockset and 4" LP hinges. (28 units)
4. On plumbing works, supply and installation of the following new fixtures:
 - a. water closet complete with pedestal type lavatory, lavatory faucet, bidet sprayer and water supply fittings and installation accessories, colored (28 sets).
 - b. Shower set complete with valve and faucet (28 units)
5. On electrical works, replacement/installation of the following:
 - a. all electrical wiring lines using THHN/THWN (Phiflex/Phelpdodge or app. Equal).
 - b. ACU outlets (28 sets)
 - c. convenience outlets (84 sets)
 - d. single and three gang switches with LED (168 sets)
 - e. 8" x 8" ceiling type exhaust fan (28 units)
 - f. LED pinlight, downlight, daylight, 11W (70 sets)
 - g. LED pinlight, downlight, warm light, 11W (84 sets)
 - h. LED wall lamp, warm light, 11W (24 sets)
 - i. LED ceiling lamp, daylight, 15W (28 sets)
 - j. heavy duty water heater (28 units)

Note: switches and outlets are pref. national/panasonic/eagle or any approved brand equivalent.

6. For colors/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end user sign your sample as proof of approval. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
7. *This bid bulletin does not cancel the information given in the scope of work of the issued Bill of Quantities but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop.*
8. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. In cases where there are electrical works, it is required that an electrical engineer or a master electrician be a part of contractors' team to supervise all electrical works. Likewise, master plumbers must supervise plumbing works. There must be a safety engineer as per DOLE requirement.

9. In cases of participation to two or more projects, the set of workers and foreman shall be different per project however, the set of engineers and equipment may be reused.
10. Construction safety and health program as well as construction schedule (PERT/CPM/S-Curve) shall be provided by the winning bidder.

Prepared by:


EFREN R. ROCILLO
TWG Chair



CENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member


RONALD P. PEÑA
TWG Member


ELPIDIO N. RODEROS, JR.
TWG Member

Approved by:


ENGR. ORLANDO B. DELOS REYES
Vice Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____