



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

IMPROVEMENT OF TRECE CAMPUS (SUPPLY AND INSTALLATION OF TILES) – 2 nd POSTING					
ABC: ₱ 1,579,091.18				Bill of Quantities	
COLLEGE/UNIT/CAMPUS: TRECE CAMPUS					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	TILE WORKS (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words		_____ _____ _____			

Submitted by: _____ Date: _____
 Name of Bidder/Bidder's Representative: _____
 Position: _____
 Construction Company/Contractor: _____

CAVITE STATE UNIVERSITY

SCOPE OF WORK:

A. IMPROVEMENT OF TRECE CAMPUS (SUPPLY AND INSTALLATION OF TILES) – 2nd POSTING

GENERAL NOTES:

1. The project should be finished in 60 calendar days.
2. Site inspection is a must. Verify actual condition of site. Site temporary enclosure may be blue sack or any suitable materials that may enclose the workplace.

B. Technical Description

I. Tile Works

Supply and installation of the following:

1. Ceramic tiles (locally made) 0.40m. x 0.40m. for the whole area of lower and upper ground floor and second floor of the building. Unglazed ceramic tiles for hallways and walkways. Tiles must be accented with dark colors.
2. Granite tiles with groove for the steps and ceramic tiles for the riser of all stairs.
3. Tiles must be installed by using tile adhesive and finished with appropriate tile grout.
4. For colors/ types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end-user sign your sample as proof of approval. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
5. All affected areas including doors, flooring, and walls affected by tile works should be retouched/ plain cement finish.

- C.** See plans/consult the end-user and project inspector for details and extent of work. The silence of specifications, plans, special provisions and supplementary specifications as to any detail, or the apparent omission therein of detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.