



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite, Philippines

☎ (046) 4150-010 / 📠 (046) 4150-0013 loc 203
www.cvsu.edu.ph

INVITATION TO SUBMIT QUOTATION
Project Taguyod (Straight Contract)

1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project "**Project Taguyod (Straight Contract)**" with an Approved Budget for the Contract (ABC) of **Two Hundred Forty-Nine Thousand Nine Hundred Thirty-Four Pesos and 96/100 Only (PhP 249,934.96)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.	1	Lot	Project Taguyod (Straight Contract)	249,934.96	249,934.96
TOTAL AMOUNT					249,934.96

2. Delivery Period: ____ calendar days from the receipt of P.O.
3. Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
4. Warranty shall be for a period of six (6) months for supplies and materials. Warranty for equipment must not be less than one (1) year from the date of acceptance and shall be accompanied with Warranty Certificate.
5. The quotation must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of January 30, 2023**.

Address : Procurement Office, Administration Building
Cavite State University
Indang, Cavite
E-mail : procurementoffice@cvsu.edu.ph / rfqmain@cvsu.edu.ph
Telefax : (046) 862-0852

6. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


ROSELYN M. MARANAN
BAC Secretary, Goods and Consulting Services



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

NAME OF PROJECT: PROJECT TAGUYOD (BY STRAIGHT CONTRACT)					
ABC: ₱ 249,934.96				Bill of Quantities	
COLLEGE/UNIT/CAMPUS: CvSU INDANG CAMPUS					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	Concrete Works (Pesos _____ _____ and _____ centavos)				
II	Masonry Works (Pesos _____ _____ and _____ centavos)				
III	Tile Works (Pesos _____ _____ and _____ centavos)				
IV	Carpentry Works (Pesos _____ _____ and _____ centavos)				
V	Miscellaneous Works (Pesos _____ _____ and _____ centavos)				
VI	Electrical Works (Pesos _____ _____ and _____ centavos)				

VII	Plumbing Works (Pesos _____ _____ and _____ centavos)				
VIII	Painting Works (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL _____					
Write grand total in words _____ _____ _____					

Submitted by: _____ Date: _____

Name of Bidder/Bidder's Representative: _____

Position: _____

Construction Company/Contractor: _____

SCOPE OF WORKS:

A. PROJECT TAGUYOD

1. The project should be finished for 30 calendar days.
2. Actual site inspection is a must.
3. The area should be cleared/cleaned before and after the construction works.

B. TECHNICAL DESCRIPTION

I. Concrete and Masonry Works

- A. Cast-in-place concrete
 1. Concrete works include the construction of concrete countertop at Pantry.
 2. Strength of concrete to be adopted shall be **3,000 psi**
 3. Provide necessary tools and equipment needed for concrete works
- B. Steel reinforcement
 1. Use deformed bar grade 33.
 2. Provide necessary tools and equipment needed for steel works.

II. Masonry Works

- A. Countertop
 1. Installation of CHB reinforced with 10 mm Ø deformed bar spaced at 0.60 m. on center every three layers.
 2. Masonry works should be plastered plain cement.

III. Tile Works

- A. Pantry Area
 1. Provide 40cm x 40cm non-skid tiles for flooring of pantry.
 2. Provide 60cm x 60cm ceramic tiles for countertop.
 3. Maintain 3 mm gap.
 4. Provide necessary tools and equipment needed for tile works.

Note: Design and color of tiles will depend upon the preference of the end-user.

IV. Carpentry Works

A. Formworks

1. Provide necessary form lumber and scaffolding needed for the completion of the project.

B. Drywall

1. Use 2.40m x 1.20m x 12mm thick Ordinary Gypsum Board both faces of drywall.
2. Use 32mm x 102mm x 0.80mm thick metal track
3. Use 32mm x 102mm x 0.80mm thick metal studs.
4. Provide necessary tools and equipment needed for carpentry works.

V. Miscellaneous Works

A. Supply and Installation of Doors

1. D1 - 2.10m x 1.60m, 1 set, Double Swing Door with complete accessories at Session Hall.
2. D2 - 2.10m x 1.00m, 1 set, Solid Panel Door with complete accessories at Pantry.
3. D3 - 2.10m x 0.60m, 1 set, PVC Panel Door with complete accessories at Comfort Room.
4. D4 - 2.10m x 0.80m, 2 sets, Aluminum Door with complete accessories at Shower Room and Toilet.

VI. Electrical Works

A. Roughing - Ins

1. Installation of wiring/conductors and PVC conduits/junction box/utility box from existing connection line.
 - THHN stranded wire, phelp dodge or approved equal.
 - PVC conduit orange pipe with sizes as indicated on the plan.
 - Utility and junction boxes should be PVC & deep type.
 - Use 2.00 sq.mm and 3.50 sq.mm for lighting and power connection respectively.
2. Installation of electrical fixtures/switches/outlets and other electrical devices.
 - Switches (Bticino, National or approved equal)
 - Convenience outlet (Bticino, National or approved equal)
 - **Pinlight with led 9W bulb (3 sets)**
 - **2-18W LED Flourescent lamp with aluminum louver diffuser (2 sets)**
3. Consult plan and inspectors for details and extent of work.

VII. Plumbing Works

A. Water Supply Line

1. Adopt PPR Pipes and fittings for water line (1/2")
2. Tapping to the source is included.
3. No pipe should be embedded without testing it to leak.

B. Sewer Line

1. Adopt PVC heavy duty orange pipes and fittings.

C. Fixture

1. Provide the following:
 - a. Floor drain, 4" with cover and anti-odor (3 pc.)
 - b. Faucet (4 pc.)
 - c. Kitchen Sink, Single Bowl (1 set)
 - d. Water closet (1 set)
 - e. Bidet (1 set)
 - f. Shower head set (1 set)

VIII. Painting Works

1. Treat the surface with concrete neutralizer. Mix one part with 16 parts water by volume.
2. Apply Latex flat as primer. Repair minor surface imperfections with a suitable putty. Let dry, then sand.
3. Apply at least two coats of colored dirt resisting semi gloss latex paint (factory mixed).

Note: Color of paint will depend upon the preference of the end-user.

Paints and its accessories should be BOYSEN or approved equal.