



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

NAME OF PROJECT: PROPOSED FRONT OFFICE COUNTER FOR HOSTEL ABC: ₱196,170.16 COLLEGE/UNIT/CAMPUS: CvSU-BACOOOR CAMPUS					
					Bill of Quantities
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	CARPENTRY WORKS (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words					_____ _____ _____

Submitted by: _____ Date: _____

Name of Bidder/Bidder's Representative: _____

Position: _____

Construction Company/Contractor: _____

A. PROPOSED FRONT OFFICE COUNTER FOR HOSTEL

1. The project must be finished in 30 calendar days.

B. TECHNICAL DESCRIPTION

I. Carpentry Works

1. Provide 20mm thk x 4" x 8" laminated MDF Board Gray Finish.
2. Use beige and brown color for leather cover. See attached plans for details.
3. Provide 14" long drawer slides, steel drawer handles and drawer locks with keys.
4. Fabrication and installation of synthetic granite, 0.40m x 4.10m