



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR CCJ AND INFIRMARY NETWORK CONNECTION**

**ABC: Php 1,405,190.00**

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Distribution Switch	<ul style="list-style-type: none"> <li>• CATALYST 9200L 24-PORT DATA</li> <li>• 4X1G DISTRIBUTION SWITCH</li> </ul>	170,000.00	170,000.00
2	2unit	Access Switch	<ul style="list-style-type: none"> <li>• CBS350-24T-4G-EU Cisco CBS350 managed 24-port GE</li> <li>• 4X1G SFP CON-SNT-CBS35UE2 SNTC-8X5XNBD CBS350 MANAGED 24- PORT GE</li> <li>• 4X1G SFP</li> </ul>	38,000.00	76,000.00
3	1lot	(2) Network Cabinet Box  (15) UTP patch cord	<ul style="list-style-type: none"> <li>•12RU Network Rack</li> <li>•3meter, Stranded Category 6</li> </ul>	50,650.00	50,650.00
4	4unit	SFP Transceiver BASE-LX	<ul style="list-style-type: none"> <li>•GLC-LH-SMD= 1000BASE-LX/LH SFP TRANSCEIVER MODULE</li> </ul>	42,000.00	168,000.00
5	1lot	(2) SFP Transceiver BASE-T  (8) Fiber Optic Patch Cord  (23) UTP patch cord  (800pcs)Fiber Optic Cable	<ul style="list-style-type: none"> <li>• GLC-TE 1000BASE-T SFP TRANSCEIVER MODULE FOR CATEGORY</li> <li>•LC/UPC-LC/UPC/2mtr</li> <li>•2meter, Stranded Category 6</li> <li>•Fiber Optic Cable, 8core Outdoor, Singlemode, armored, with messenger wire (meters)</li> </ul>	451,125.00	451,125.00
6	1lot	(3) Fiber Optic Patch Panel	<ul style="list-style-type: none"> <li>• 1U</li> <li>• 12 LC/UPC</li> <li>• with splice tray</li> </ul>	50,000.00	50,000.00

		(16) LC/UPC Pigtails  (10) Information Outlet  (15) Wall Outlet Faceplate for RJ45	<ul style="list-style-type: none"> <li>• Singlemode 900um simplex 1mtr</li> <li>• Category 6</li> <li>• Wall Outlet Faceplate for RJ45</li> </ul>		
7	4box	UTP Cable	<ul style="list-style-type: none"> <li>• Category 6</li> <li>• 4-pair (305)</li> </ul>	15,500.00	62,000.00
8	4unit	Patch Panel	<ul style="list-style-type: none"> <li>• 24-port Category 6</li> </ul>	16,000.00	64,000.00
9	1lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>• PVC pipes and fittings</li> <li>• Pole attachments</li> <li>• Cable termination and consumables</li> </ul>	324,275.00	313,415.00
<b>GRAND TOTAL:</b>					<b>₱1,405,190.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF BACOR CAMPUS.**

ABC: Php 650,300.00

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	2	UTP Cable	•Cat5e 305m (preferably Belden)	6,500.00	13,000.00
4	1	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00
5	10	RJ45 Wall mount socket	•RJ45 Wall mount socket	500.00	5,000.00
6	4	Patch Panel	•24 port CAT5E	4,000.00	16,000.00
7	1	UPS	<ul style="list-style-type: none"> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> </ul>	10,000.00	10,000.00
8	100	RJ45 Connector	•RJ45 Connector	5.00	500.00
9	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> </ul>	185,800.00	185,800.00

			• Cable termination and consumables		
<b>GRAND TOTAL:</b>					<b>₱650,300.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF CARMONA CAMPUS.**

ABC: Php 657,300.00

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	1lot	Network Manageable Workgroup Switch  Network Cabinet Box	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> <li>• 19" opening-600MM</li> <li>• Glass Front Door with camlock</li> <li>• Detachable side panels with snaplock and camlock</li> <li>• Top cover with 2x fans</li> <li>• Powerstrip 2CO</li> <li>• Cagenuts and Bolts</li> <li>• Power Coated Finish</li> </ul>	60,000.00	60,000.00
3	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>• 6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>• Front Cable management c/w Cable Ring</li> <li>• Vertical Cable Tray</li> <li>• 4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>• Set of HeavyDuty Castor Wheels</li> <li>• Base Frame with Provision of Cable Entrance</li> <li>• Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00

4	1lot	<p>2 box UTP Cable</p> <p>20 pcs RJ45 Wall mount socket</p> <p>4pcs Patch Panel</p> <p>1pc UPS</p> <p>100pcs RJ45 Connector</p>	<ul style="list-style-type: none"> <li>•Cat5e 305m (preferably Belden)</li> <li>•RJ45 Wall mount socket</li> <li>•24 port CAT5E</li> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> </ul> <p>RJ45 Connector</p>	50,000.00	50,000.00
5	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> <li>•Cable termination and consumables</li> </ul>	187,800.00	187,300.00
<b>GRAND TOTAL:</b>					<b>₱657,300.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
**Don Severino de las Alas Campus**  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF CAVITE CITY CAMPUS.**

**ABC: Php 666,400.00**

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	1lot	(3) UTP Cable  (20) RJ45 Wall mount socket  (4) Patch Panel  (1)UPS  (100)RJ45 Connector	<ul style="list-style-type: none"> <li>•Cat5e 305m (preferably Belden)</li> <li>•RJ45 Wall mount socket</li> <li>•24 port CAT5E</li> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> <li>•RJ45 Connector</li> </ul>	56,000.00	56,000.00
4	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> </ul>	60,000.00	60,000.00

			<ul style="list-style-type: none"> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>		
5	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> <li>•Cable termination and consumables</li> </ul>	190,400.00	190,400.00
<b>GRAND TOTAL:</b>					<b>₱666,400.00</b>





Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF GENERAL TRIAS CAMPUS.**

ABC: Php 704,900.00

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	1lot	(3)UTP Cable  (1) 19" Network Cabinet Box  (15)RJ45 Wall mount socket  (4)Patch Panel  (2)UPS  (100)RJ45 Connector	<ul style="list-style-type: none"> <li>•Cat5e 305m (preferably Belden)</li> <li>•Glass Front door w/ camlock / Detachable side panels</li> <li>•Top Cover w/ 2x fans</li> <li>•Cagenuts and Bolts</li> <li>•Power Coated Finish</li> <li>•RJ45 Wall mount socket</li> <li>•24 port CAT5E</li> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> <li>•RJ45 Connector</li> </ul>	83,500.00	83,500.00

4	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00
5	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> <li>•Cable termination and consumables</li> </ul>	201,400.00	201,400.00
<b>GRAND TOTAL:</b>					<b>₱704,900.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF IMUS CAMPUS.**

**ABC: Php 662,900.00**

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	1lot	(3)UTP Cable  (15)RJ45 Wall mount socket  (4)Patch Panel  (1)UPS  (100)RJ45 Connector	<ul style="list-style-type: none"> <li>•Cat5e 305m (preferably Belden)</li> <li>•RJ45 Wall mount socket</li> <li>•24 port CAT5E</li> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> <li>•RJ45 Connector</li> </ul>	53,500.00	53,500.00
4	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> </ul>	60,000.00	60,000.00

			<ul style="list-style-type: none"> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>		
5	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> <li>•Cable termination and consumables</li> </ul>	189,400.00	189,400.00
<b>GRAND TOTAL:</b>					<b>₱662,900.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF SILANG CAMPUS.**

ABC: Php 701,900.00

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	1lot	(2)UTP Cable  (1)Network Cabinet Box  (20)RJ45 Wall mount socket  (4)Patch Panel  (2)UPS  (100)RJ45 Connector	<ul style="list-style-type: none"> <li>•Cat5e 305m (preferably Belden)</li> <li>•19"</li> <li>•Glass Front door w/ camlock / Detachable side panels</li> <li>•Top Cover w/ 2x fans</li> <li>•Cagenuts and Bolts</li> <li>•Power Coated Finish</li> <li>•RJ45 Wall mount socket</li> <li>•24 port CAT5E</li> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> <li>•RJ45 Connector</li> </ul>	79,500.00	79,500.00

4	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00
5	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> <li>•Cable termination and consumables</li> </ul>	202,400.00	202,400.00
<b>GRAND TOTAL:</b>					<b>₱701,900.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF TANZA CAMPUS.**

ABC: Php 596,750.00

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	1lot	(1)Network Manageable Workgroup Switch  (2)UTP Cable  (10)RJ45 Wall mount socket  (2)Patch Panel  (1)UPS  (50)RJ45 Connector	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> <li>• Cat5e 305m (preferably Belden)</li> <li>• RJ45 Wall mount socket</li> <li>• 24 port CAT5E</li> <li>• 1100VA / 660watts</li> <li>• iec c13 socket</li> <li>• 2 battery</li> <li>• RJ45 Connector</li> </ul>	66,250.00	66,250.00

3	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00
4	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>•PVC pipes and fittings</li> <li>•Pole attachments</li> <li>•Cable termination and consumables</li> </ul>	170,500.00	170,500.00
<b>GRAND TOTAL:</b>					<b>₱596,750.00</b>





Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF TRECE CAMPUS.**

ABC: Php 708,400.00

WItem No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	1lot	(3)UTP Cable  (1)Network Cabinet Box  (20)RJ45 Wall mount socket  (4)Patch Panel  (2)UPS  (100)RJ45 Connector	<ul style="list-style-type: none"> <li>•Cat5e 305m (preferably Belden)</li> <li>•19"</li> <li>•Glass Front door w/ camlock / Detachable side panels</li> <li>•Top Cover w/ 2x fans</li> <li>•Cagenuts and Bolts</li> <li>•Power Coated Finish</li> <li>•RJ45 Wall mount socket</li> <li>•24 port CAT5E</li> <li>•1100VA / 660watts</li> <li>•iec c13 socket</li> <li>•2 battery</li> <li>•RJ45 Connector</li> </ul>	86,000.00	86,000.00

4	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>•6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>•Front Cable management c/w Cable Ring</li> <li>•Vertical Cable Tray</li> <li>•4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>•Set of HeavyDuty Castor Wheels</li> <li>•Base Frame with Provision of Cable Entrance</li> <li>•Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00
5	1 lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>• PVC pipes and fittings</li> <li>• Pole attachments</li> <li>• Cable termination and consumables</li> </ul>	202,400.00	202,400.00
<b>GRAND TOTAL:</b>					<b>₱708,400.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF NAIC CAMPUS.**

ABC: Php 440,460.00

Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
2	lot	(2)Fiber Optic Patch Panel  (2)UTP Cable  (1)Network Cabinet Box  (16)LC/UPC Pigtaills (8)Fiber Optic Patch Cord (20)RJ45 Wall mount socket (4)Patch Panel  (2)UPS	<ul style="list-style-type: none"> <li>•1u, 12LC/UPC with splice tray</li> <li>•Cat5e 305m (preferably Belden)</li> <li>•19"</li> <li>•Glass Front door w/ camlock / Detachable side panels</li> <li>•Top Cover w/ 2x fans</li> <li>•Cagenuts and Bolts Power Coated Finish</li> <li>•Singlemode 900um, simplex, 1 meter</li> <li>•LC/UPC-LC/UPC/2mtr/SM Duplex</li> <li>•RJ45 Wall mount socket</li> <li>• 24 port CAT5E</li> <li>• 1100VA / 660watts</li> <li>• iec c13 socket</li> </ul>	254,758.00	254,758.00

		(100)RJ45 Connector	<ul style="list-style-type: none"> <li>• 2 battery</li> <li>• RJ45 Connector</li> </ul>		
		(300m)Fiber Optic Cable	<ul style="list-style-type: none"> <li>• 8 core outdoor</li> <li>• singlemode, armored, with messenger wire</li> </ul>		
3	1lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>• PVC pipes and fittings</li> <li>- Pole attachments</li> <li>- Cable termination and consumables</li> </ul>	125,702.00	125,702.00
<b>GRAND TOTAL:</b>					<b>₱440,460.00</b>



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino de las Alas Campus  
 Indang, Cavite  
 ☎ (046) 862-0852  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**SUPPLY, DELIVERY, AND INSTALLATION OF ICT EQUIPMENT FOR INITIAL ESTABLISHMENT OF LOCAL AREA NETWORK OF ROSARIO CAMPUS.**

ABC: Php 1,157,600.00


Item No.	Qty./ Unit	Item Description	Specifications	Unit Price (Php)	Total Price (Php)
1	1unit	Network Manageable Cisco Core Switch	<ul style="list-style-type: none"> <li>• Catalyst Network Essential, 24 port license</li> <li>• 24 ethernet port Gigabit / POE+</li> <li>• 4x10G Uplink SFP</li> <li>• Config 5 power supply blank</li> <li>• North America AC Type A power Cable</li> </ul>	300,000.00	300,000.00
2	2unit	Network Manageable Workgroup Switch	<ul style="list-style-type: none"> <li>• 2xGigabit SFP Combo + 2xGigabit SFP</li> <li>• Layer 3 Supported</li> <li>• Preferably Cisco Managed 24 port FE</li> <li>• Standard 802.1d Spanning Tree, RSTP and MSTP Support</li> <li>• Support 4096 VLAN's simultaneously</li> <li>• 12.8 Gbps switching capacity</li> </ul>	30,000.00	60,000.00
3	1unit	42u Network Rack Cabinet finished with powder coating	<ul style="list-style-type: none"> <li>• 6 x 4-inch Top Fan Tray with Guard &amp; Filter (Low Noise)</li> <li>• Front Cable management c/w Cable Ring</li> <li>• Vertical Cable Tray</li> <li>• 4 x Panel Mount with Unit Indication &amp; Silk Screen Numbering</li> <li>• Set of HeavyDuty Castor Wheels</li> <li>• Base Frame with Provision of Cable Entrance</li> <li>• Vented Equipment Fixed Tray</li> </ul>	60,000.00	60,000.00
4	1lot	(2)Fiber Optic Patch Panel (16)LC/UPC Pigtailed (8)Fiber Optic Patch Cord (20)RJ45 Wall mount socket (4)Patch Panel (2)UPS	<ul style="list-style-type: none"> <li>• 1u, 12LC/UPC with splice tray</li> <li>• Singlemode 900um</li> <li>• simplex, 1 meter</li> <li>• LC/UPC-LC/UPC/2mtr/SM Duplex</li> <li>• RJ45 Wall mount socket</li> <li>• 24 port CAT5E</li> <li>• 1100VA / 660watts</li> </ul>	406,858.00	406,858.00


		(100)RJ45 Connector	<ul style="list-style-type: none"> <li>• iec c13 socket</li> <li>• 2 battery</li> <li>• RJ45 Connector</li> </ul>		
		(3)UTP Cable	<ul style="list-style-type: none"> <li>• Cat5e 305m (preferably Belden)</li> </ul>		
		19" Network Cabinet Box	<ul style="list-style-type: none"> <li>•Glass Front door w/ camlock / Detachable side panels</li> <li>•Top Cover w/ 2x fans</li> <li>•Cagenuts and Bolts</li> <li>Power Coated Finish</li> </ul>		
		(600m)Fiber Optic Cable	<ul style="list-style-type: none"> <li>•8 core outdoor singlemode, armored, with messenger wire</li> </ul>		
5	1lot	Labor & rough-ins	<ul style="list-style-type: none"> <li>• PVC pipes and fittings</li> <li>• Pole attachments</li> <li>• Cable termination and consumables</li> </ul>	330,742.00	330,742.00
<b>GRAND TOTAL:</b>					<b>₱1,157,600.00</b>

Prepared by:

  
**ANZLEY R. CRUSIS**  
 End-User

Noted/Certified Correct:

  
**DINDO C. MARGES**  
 TWG Member, Computer and Office Equipment

  
**EMELINE C. GUEVARRA**  
 TWG Chair, Computer and Office Equipment