



BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)

SUPPLEMENTAL / BID BULLETIN NO. 2

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Construction of HRM Hostel Building at Silang Campus (CvSU-BAC-INFRA-23-011)** with an **ABC of ₱ 17,217,065.83**:

1. Site inspection is a must.
2. There are four (4) sheets of plans issued as bid bulletin for additional information and clarification. Structural details of stairs, the service entrance post, the riser diagram and some revisions on the schedule of loads should be noted.
3. Demolition works to clear the area for building construction is included. There is a need to dismantle some existing structures that may affect the new building to be constructed.
4. Concrete works:
 - a) Provide 2 - 10 mm 0 stiffener bars to all beams.
 - b) Concrete tables are 0.60 m in width, 0.10 m thick and to be reinforced with 10 mm dia deformed bars spaced at 0.15 both ways.
5. Masonry/Tile Works:
 - a) Stage construction is included. It is elevated at 0.60 m. and finished with colored ceramic tiles 0.40 m x 0.40 m and granite tiles with groove for the steps.
 - b) Concrete counter for laundry area should be granite slab finished including 0.60 m of its wall.
 - c) All concrete counters should be supported with CHB wall in a maximum distance of 2.0 m; this wall should be tile finished.
6. Trusses and Roofing Works
 - a) Provide ga 26 (0.5mm) pre painted ridge roll for roofing works.
7. Miscellaneous Works
 - a) D-2 Aluminum door shall be installed. See plan.
 - b) Concrete working tables should be provided with stainless sheet ga 16 (304) including 0.60 m on its wall.
 - c) D6 should be aluminum with louver and D7 should be aluminum with decorative frosted glass.
8. Electrical Works
 - a) Service entrance post shall be provided. See additional plans.
 - b) Provide ACU outlets and Special Purpose Outlets.
 - c) Provide 3-way switches for the stairs.
9. Plumbing Works
 - a) Catch basins should be provided and to be installed with the RCP sizes as shown in the plan.
 - b) Tap to the disposal area.
10. *The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. Consult the plan and the scope of work for the extent of tasks of the contract. As possible, let the end user or the inspector sign your sample as proof of approval.*
11. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails.
12. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/ bid bulletin to the BOQ and include in the financial envelop.*

Prepared by:



EFREN R. ROCILLO
TWG Chair



CENE M. BAGO
TWG Member



LARRY E. ROCELA
TWG Member



RONALD P. PEÑA
TWG Member



ELPIDIO N. RODEROS, JR.
TWG Member

Approved by:



MA. AGNES P. NUESTRO, Ph.D.
Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____