# Republic of the Philippines

## **CAVITE STATE UNIVERSITY**

## Don Severino de las Alas Campus

Indang, Cavite, Philippines

(046) 4150-010 / ₹ (046) 4150-0013 (0c 203)

www.cvsu.edu.ph

# INVITATION TO SUBMIT QUOTATION Improvement of Silang Campus - Construction of University Signage (Straight Contract)

 The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project "Improvement of Silang Campus - Construction of University Signage (Straight Contract)" with an Approved Budget for the Contract (ABC) Three Hundred Sixty-Three Thousand Nine Hundred Seventy-Three Pesos and 61/100 Only (PhP 363,973.61). Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost	
1.	1	Lot	Improvement of Silang Campus - Construction of University Signage (Straight Contract)	363,973.61	363,973.61	
	TOTAL AMOUNT					

- Delivery Period: calendar days from the receipt of P.O.
- Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
- Warranty shall be for a period of six (6) months for supplies and materials. Warranty for equipment must not be less than one (1) year from the date of acceptance and shall be accompanied with Warranty Certificate.
- The quotation must be submitted to the Procurement Office through mail, fax or email at the contact details listed below on or before 5:00 PM of May 23, 2023.

Address : Procurement Office, Administration Building,

Cavite State University

Indang, Cavite

E-mail : procurementoffice@cvsu.edu.ph / rfqmain@cvsu.edu.ph

Telefax : (046) 889-6373

6. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.

ROSELYN M. MARANAN

BAC Secretary, Goods and Consulting Services



## **BILL OF QUANTITIES**

COLLE	P 363,973.61 EGE/UNIT/CAMPUS: CvSU SILANG CA	Bill of Quantities			
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
_	Earthworks (Pesos				
	and centavos)				
II	Concrete, Masonry and Tile Works (Pesos				
	and centavos)				
III	Miscellaneous Works (Pesos				
	and centavos)				
	GRAND TOTAL				
	Write grand total in words				

## SCOPE OF WORKS:

## A. IMPROVEMENT OF SILANG CAMPUS

(Construction of University Signage)

Site inspection is a must to verify actual condition of site.

V01-2018-06-14

2. The project should be finished for 25 calendar days.

#### B. TECHNICAL DESCRIPTION

- Earthworks
  - A. Excavation / chipping / backfilling / clearing
    - 1. This work includes excavation for column footings.
    - The area should be cleared before and after the construction work. Unusable used form works, excessive soil fill and all other unwanted debris of construction works should be disposed at designated area.
- II. Concrete, Masonry and Tile Works
  - A. Concrete, Masonry and Tile
    - This work includes concreting of column footings and columns.
    - Strength of concrete to be adopted shall be 3,500 psi @ 28 days.
    - Concrete pedestal should be finished with bricks.
    - Concrete molding for every column is included.
    - Provide necessary tools and equipment needed for concrete and masonry works.
  - B. Steel reinforcement
    - 1. Use deformed bar grade 40.
    - Provide necessary tools and equipment needed for steel works.
    - 3. See plan for details and extent of work.
- III. Miscellaneous Works
  - Supply and installation of stainless arch with signage.
    - Signage, made of stainless steel mirror finish 1/16" thickness, 12" height x 8" wide, in proportion, times new roman font compressed, with 1-1/2" stainless build-up sidings with 2 ½" (2.0) stainless pipe holder and 2" (2.0) stainless pipe member/framing with green aluminum composite panel back ground.

#### CAVITE STATE UNIVERSITY

 Signage, made of stainless steel mirror finish 1/16" thickness, 6.5" height x 4.5" wide, in proportion, times new roman font compressed, with 1" stainless build-up sidings.

#### SILANG CAMPUS

- University and municipal seal made of stainless steel mirror finish 1/16" thickness, 12" height x 12" wide, in proportion.
- Supply and Installation of 5 sets of flood light (20W). Tap to the source.
- IV. See plans for details and extent of work.