



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite, Philippines
☎ (046) 889-6373
www.cvsu.edu.ph

INVITATION TO SUBMIT QUOTATION
Installation of Fire Protection for CvSU Cavite City Campus Main Building (Straight Contract)


1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project **"Installation of Fire Protection for CvSU Cavite City Campus Main Building (Straight Contract)"** with an Approved Budget for the Contract (ABC) **Five Hundred Seventy-Two Thousand Eight Hundred Twenty-Four Pesos and 22/100 Only (PhP 572,824.22)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

| Item No. | Quantity | Unit | Description | Unit Cost | Total Cost |
|---------------------|----------|------|---|------------|-------------------|
| 1. | 1 | Lot | Installation of Fire Protection for CvSU Cavite City Campus Main Building (Straight Contract) | 572,824.22 | 572,824.22 |
| TOTAL AMOUNT | | | | | 572,824.22 |

2. Delivery Period: ____ calendar days from the receipt of P.O.
3. Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
4. Warranty shall be for a period of six (6) months for supplies and materials. Warranty for equipment must not be less than one (1) year from the date of acceptance and shall be accompanied with Warranty Certificate.
5. The quotation must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of July 26, 2023.**

Address : Procurement Office, Administration Building
Cavite State University
Indang, Cavite
E-mail : procurementoffice@cvsu.edu.ph / rfqmain@cvsu.edu.ph
Telefax : (046) 889-6373

6. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


ROSELYN M. MARANAN
BAC Secretary, Goods and Consulting Services



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino Delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

| NAME OF PROJECT: INSTALLATION OF FIRE PROTECTION FOR CAVITE CITY CAMPUS MAIN BUILDING (STRAIGHT CONTRACT) ABC: ₱ 572,824.22 COLLEGE/UNIT/CAMPUS: Cvsu CAVITE CITY CAMPUS | | | | | |
|---|--|------|----------|---------------------------|-------------------------|
| | | | | Bill of Quantities | |
| Item No. | Description | Unit | Quantity | Unit Price (Pesos) | Amount (Pesos) |
| I | Mobilization (Pesos _____ _____ and _____ centavos) | | | | |
| II | Fire Protection Works (Pesos _____ _____ and _____ centavos) | | | | |
| GRAND TOTAL | | | | | _____ |
| Write grand total in words | | | | | _____ _____ _____ |

Submitted by: _____ Date: _____

Name of Bidder/Bidder's Representative: _____

Position: _____

Construction Company/Contractor: _____

SCOPE OF WORKS

INSTALLATION OF FIRE PROTECTION FOR Cvsu CAVITE CITY CAMPUS MAIN BUILDING

A. GENERAL DESCRIPTION

1. The project should be finished for 60 calendar days.
2. Actual site inspection is a must.
3. This set of specifications shall govern the methods of construction and the kinds of materials to be used for the proposed project shown in the plans and detailed drawings.
4. The plans, detailed drawings and these specifications shall be considered as complementing each other, so that what is mentioned or shown in one, although not

mentioned or shown in the other, shall be considered as appearing on both. In case of conflict between the two, the same should be referred to the project inspector for resolution.

5. All parts of the construction shall be finished with first class workmanship, to the fullest talent and meaning of the plans and these specifications, and to the entire satisfaction of the project inspector and the end-user.

B. TECHNICAL DESCRIPTION

I. Mobilization

This work includes site preparation, temporary enclosure, mobilization, demobilization, office, bunkhouse, comfort rooms and etc.

II. Fire Protection Works

1. This work includes the fabrication, complete in all details, of fire protection works at the subject premises, the installation, except those portions shall be in accordance with governing Codes and Regulations and with the specifications, except where the same shall conflict with the codes, etc. which, later shall be govern. The requirements in regards to materials and workmanship specify the required standards for the furnishing of all labor, materials and appliances necessary for the complete installation of the work specified herein and indicated on the drawings.
2. The contractor required to visit the site and to ascertain himself as to the local conditions and facilities that may affect his work. He will be deemed to have done this before preparing his proposal and any subsequent claims on the ground of inadequate or inaccurate information will not be entertained.
3. Supply and Installation of the following:
 - a. 60 units smoke detector
 - b. 1 unit heat detector
 - c. 29 pcs. stored pressure type HCFC 123 CEA fire extinguisher
 - d. 4 units fire hose with cabinet
 - e. Dry stand pipe 3" with siamese fitting
 - f. 1 set fire alarm control panel
 - g. 7 sets fire alarm bell with control
4. Include testing and commissioning.