



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite, Philippines
(046) 4150-010 / (046) 4150-0013 loc 203
www.cvsu.edu.ph

INVITATION TO SUBMIT QUOTATION
Labor for Construction of Sidewalk for Proper Crossing Beside Gate 1 (By
Administration – Pakyaw Labor Group)

1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project **“Labor for Construction of Sidewalk for Proper Crossing Beside Gate 1 (By Administration – Pakyaw Labor Group)”** with an Approved Budget for the Contract (ABC) **One Hundred Twenty-One Thousand One Hundred Twenty-Six Pesos and 40/100 Only (PhP 121,126.40)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.	1	Lot	Labor for Construction of Sidewalk for Proper Crossing Beside Gate 1 (By Administration – Pakyaw Labor Group)	121,126.40	121,126.40
TOTAL AMOUNT					121,126.40

2. Delivery Period: ____ calendar days from the receipt of P.O.
3. Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
4. Warranty shall be for a period of six (6) months for supplies and materials. Warranty for equipment must not be less than one (1) year from the date of acceptance and shall be accompanied with Warranty Certificate.
5. The quotation must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of July 06, 2023**.

Address : Procurement Office, Administration Building
Cavite State University
Indang, Cavite
E-mail : procurementoffice@cvsu.edu.ph / rfqmain@cvsu.edu.ph
Telefax : (046) 889-6373

6. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


ROSELYN M. MARANAN
BAC Secretary, Goods and Consulting Services



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino Delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

NAME OF PROJECT: CONSTRUCTION OF REPAIR OF SIDEWALK FOR PROPER CROSSING BESIDE GATE 1 (BY ADMINISTRATION – PAKYAW LABOR GROUP) ABC: ₱ 121,126.40 COLLEGE/UNIT/CAMPUS: CvSU INDANG CAMPUS					
Bill of Quantities					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	Concrete, Masonry and Formworks (Pesos _____ _____ and _____ centavos)				
II	Steel Works (Pesos _____ _____ and _____ centavos)				
III	Painting Works (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words					_____ _____ _____

Submitted by: _____ Date: _____

Name of Bidder/Bidder's Representative: _____

Position: _____

Construction Company/Contractor: _____

SCOPE OF WORKS:

A. CONSTRUCTION AND REPAIR OF SIDEWALK FOR PROPER CROSSING BESIDE GATE 1

1. The project must be finished in 25 working days

2. Actual site inspection is a must.
3. The area should be cleared before and after the construction work at least twelve meters away from the job site. Unusable formworks, excessive soil fill and all other unwanted debris of installation works should be disposed properly.

B. TECHNICAL DESCRIPTION

I. Concrete and Masonry Works

1. Excavate and level the ground for the proposed concreting of side walk.
2. 0.05 mtr. Thickness gravel fill
3. 0.10 meters the thickness of the sidewalk flooring, the mixture is 1-4-6
4. The surface of the flooring will be designed with the same design as the existing one

II. STEEL WORKS

1. Fabricate grills with railing and install according to plan
2. Remove rust and clean before painting with primer
3. Be sure to clean before applying primer.
4. Apply two coat of automotive paint enamel

III. PAINTING WORKS

1. Apply primer for the first coat, and then apply 2 coats of the final color paint.
2. Apply paint those designed on the flooring with a textured tile red.

IV. Note

1. See/consult end user for details/extent of work. The silence of specification, plans, special provision and supplementary specifications as to any detail, or the apparent omission therein of a detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.
2. All works will be facilitated by PPS office.
3. All tools and equipment necessary for executing the work will be provided by Contractor.
4. Works that are necessary but are not cited in the above specifications will be facilitated by PPS office.
5. Materials that are necessary but are not included in the above program of works will be provided by the end user.
6. No modifications will be done without the approval of end user, project inspector and implementor.
7. Verify actual measurement on site.