



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

IMPROVEMENT OF BACOR CAMPUS (SUPPLY AND INSTALLATION OF STEEL DOORS)					
ABC: ₱ 1,063,144.25				Bill of Quantities	
COLLEGE/UNIT/CAMPUS: BACOR CAMPUS					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	DISMANTLING WORKS (Pesos _____ _____ and _____ centavos)				
II	MISCELLANEOUS WORKS (Pesos _____ _____ and _____ centavos)				
III	MASONRY WORKS (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words _____ _____ _____					

Submitted by: _____ Date: _____
 Name of Bidder/Bidder's Representative: _____
 Position: _____
 Construction Company/Contractor: _____

CAVITE STATE UNIVERSITY

SCOPE OF WORK:

A. IMPROVEMENT OF BACOR CAMPUS (SUPPLY AND INSTALLATION OF STEEL DOORS)

GENERAL NOTES:

1. The project should be finished in 30 calendar days.
2. There is an existing structure. Site inspection is a must to verify site condition.
3. The area should be cleared/cleaned before and after the construction work at least six meters away from the building line. Unusable used formworks, excessive soil fill and all other unwanted debris of construction works should be disposed properly.
4. Mobilization
 - a. Provide the following:
 1. Billboard
 2. Bunk house, temporary office and temporary comfort rooms
 3. Site enclosure

B. Technical Description

I. Dismantling Works

A. Demolition/Dismantling/Clearing

1. Dismantling of existing doors (60 units)
2. All dismantled doors and other unwanted debris of construction works should be disposed of properly.

II. Miscellaneous Works

1. Supply and installation of 60 sets of pre-painted steel flush doors (1.0m x 2.10m) with ¼" thick clear glass view window complete with all accessories.

III. Masonry Works

1. Damaged walls resulting from door dismantling must be restored using CHB and plastered with plain cement.

- C.** See plans/consult the end-user and project inspector for details and extent of work. The silence of specifications, plans, special provisions and supplementary specifications as to any detail, or the apparent omission therein of detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class quality are to be used or employed.