



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 3**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Rehabilitation of Hostel Tropicana (CvSU-BAC-INFRA-23-035)** with an **ABC of ₱ 14,570,682.68**:

1. Site inspection is a must. There is an existing structure. Verify actual condition of site.
  - Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
2. Painting/repainting works must be done to restore the walls affected by the installation of new doors and window units.
3. Include removal and replacement of dilapidated trusses and other roof framing members.
4. On electrical works: remove and replace the electrical system of the building to make it functional.
  - a) Supply and install 2-18W LED light tube with diffuser (77 sets) instead of 36W LED panel lighting (4').
  - b) Supply and install 2-9W LED light tube with diffuser (11 sets) instead of 18W LED panel lighting (4').
  - c) Supply and install 1-9W LED pin light, surface type (115 sets) instead of 9W LED round panel lighting.
  - d) Supply and install 1-9W LED light tube with diffuser (92 sets).
  - e) Exclude the supply and installation of chandelier lighting from the scope of work.
  - f) All deep type electrical boxes should be PVC. Exclude item number 11 from the electrical works, which pertains to the use of deep type metal boxes.

**GENERAL NOTES:**

1. The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Consult the plan and the scope of work for the extent of tasks of the contract.
2. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails. Further, whichever is advantageous to the government is given priority.
3. For concrete works: provide ready mixed concrete of specified strength.
4. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/ bid bulletin to the BOQ and include in the financial envelope.*


Prepared by:

  
**EFREN R. ROCILLO**  
TWG Chair

  
**GENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member

  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

Approved by:

  
**MA. AGNES P. NUESTRO, Ph.D.**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_