



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
**Don Severino de las Alas Campus**  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 2**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Improvement of Electrical Power System of Carmona Campus (CvSU-BAC-INFRA-23-038)** with an ABC of **₱ 6,383,469.90**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. Supply and installation of cable ladder inside the electrical house.
4. For miscellaneous works:  
Supply and installation of the following to the electrical house:
  - a. 1 set solid steel panel door (0.9m x 2.10m) complete with lever type heavy duty door knob; at least 3 pieces stainless HD 3" hinges and all other accessories.
  - b. 1 set sliding aluminum window on powder coated aluminum frame with colored glasses complete with heavy duty accessories; with grills (horizontal 12 mm round bar spaced at 0.10m on center framed by flat bar 1/4" x 1" per panel of glass window)
5. The fire alarm control panel must be addressable type.

**GENERAL NOTES:**


1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities but adds clarification to it. Please attach this added information/ bid bulletin to the BOQ and include in the financial envelope.*
2. The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Consult the plan and the scope of work for the extent of tasks of the contract.
3. In the event that discrepancies on plans and scope of work occur, generally, the scope of work prevails. Further, whichever is advantageous to the government is given priority.
4. For concrete works: provide ready mixed concrete of specified strength.
5. Materials to be used on site must be subjected to material testing which will be charged to the contractor.
6. Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy duty lever type.
7. Multi-roles are allowed for the key personnel who are the engineers and managers of the project.
8. All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.
9. Please prepare the detailed estimates with at least Arial 10 font size.




Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph


Prepared by:

  
**EFREN R. ROCILLO**  
TWG Chair


  
**GENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member

  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

Approved by:

  
**MA. AGNES P. NUESTRO, Ph.D.**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_