



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)

SUPPLEMENTAL / BID BULLETIN NO. 1

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Improvement of Agri-Eco Tourism Park (Construction of Bicycle Zipline Structure and Two Units Pavilion) (CvSU-BAC-INFRA-24-003)** with an ABC of **₱ 1,660,492.15**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. For Construction of Bicycle Zipline
 - a. Steps for the stairs shall use 1/4" thick checkered steel plate framed with 1/4" x 2" angle bars.
 - b. Tubular bars shall be 2.0 mm thick while cee purlins shall be 1.0 mm thick with sizes as indicated in the plan.
 - c. Eye bolts with nut & washer shall be installed to the columns.
 - d. Bicycle and tension lines are not included yet.
 - e. See plans/consult the end user and project inspector for further extent of works.
4. There is a revision on structural plan **S 2/4, column ties were increased for both top and bottom columns.**
5. Concrete balluster and parapet shall be installed.
6. For two units pavilion: thickness of tubular bars and cee purlins shall be 2.0 mm and 1.0 mm respectively.
7. For two units pavilion: thickness of tubular bars and cee purlins shall be 2.0 mm and 1.0 mm respectively.

GENERAL NOTES:

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities (BOQ) but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop (envelop 2).*
2. The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Further, consult the plan and the scope of work for the extent of tasks of the contract.
3. In the event that discrepancies on plans and scope of work occurs, generally, the scope of works prevails. Further, whichever is advantageous to the government is given priority.
4. For concrete works: provide ready mixed concrete of specified strength.
5. Materials to be used on site must be subjected to material testing which will be charged to the contractor.
6. Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy-duty lever type.
7. Multi-roles are allowed for the key personnel who are the engineers and managers of the project.
8. All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

Prepared by:

EFREN R. ROCILLO
TWG Chair

CENE M. BAGO
TWG Member

LARRY E. ROCELA
TWG Member

RONALD P. PEÑA
TWG Member

ELPIDIO N. RODEROS, JR.
TWG Member

TRISHA MARIE I. JULIANO
TWG Member

RYAN JANSSEN R. SANCHEZ
TWG Member

Approved by:

MA. AGNES P. NUESTRO, Ph.D.
Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____