



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 1**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Concreting of Parking Space near Inang Kalikasan (CvSU-BAC-INFRA-24-009)** with an ABC of **₱ 2,698,028.75**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. There is an additional plan showing the respective dimensions for the driveway, the parking for cars and motorcycles and the concrete pavement.
4. The slab on fill thickness shall be 150 mm.
5. Provide 150 mm thick grass paver blocks for the parking areas for cars and buses.
6. Supply and installation of the roofing of the covered walk on the entrance to parking area. (see plans)
  - a. Refer to the sizes of existing materials for the extended pipe columns, braces and lateral framings.
  - b. Curved pre-painted rib type roofing sheets (0.5 mm) on 2" x 4" x 2.0 mm tubular for purlins.

**GENERAL NOTES:**

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities (BOQ) but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop (envelop 2).*
2. The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Further, consult the plan and the scope of works as well as the end-user and inspector for the extent of tasks of the contract.
3. In the event that discrepancies on plans and scope of work occurs, generally, the scope of works prevails. Further, whichever is advantageous to the government is given priority.
4. For concrete works: provide ready mixed concrete of specified strength.
5. Materials to be used on site must be subjected to material testing which will be charged to the contractor.
6. Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy-duty lever type.
7. Multi-roles are allowed for the key personnel who are the engineers and managers of the project.
8. All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

Prepared by:

**EFREN R. ROCILLO**  
TWG Chair

**CENE M. BAGO**  
TWG Member

**LARRY E. ROCELA**  
TWG Member

**RONALD P. PEÑA**  
TWG Member

**ELPIDIO N. RODEROS, JR.**  
TWG Member

**TRISHA MARIE I. JULIANO**  
TWG Member

**RYAN JANSSEN R. SANCHEZ**  
TWG Member

Approved by:

**MA. AGNES P. NUESTRO, Ph.D.**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_