



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 1**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Improvement of College of Nursing to Increase Carrying Capacity (CvSU-BAC-INFRA-24-012)** with an ABC of **₱ 50,000,000.00**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. Demolition work for minor structures in front of the building is included as well as chipping works for anchorage of new structures to the existing.
4. There are revised/additional plans as bid bulletin.
  - a. A revised plan for roof deck floor beam plan
  - b. An additional roof beam plan for the roof deck. *Please take note that this is for the entire roof deck.*
  - c. Additional 5 sheets plan for the fire protection
5. Gravel fill shall be 0.05 meter thick.
6. Water proofing for all comfort rooms shall be included.
7. Column details from 4th floor to roof beam shall use the third floor column schedule.
8. For plumbing works:
  - a. Provide 5 sets under the counter lavatories complete with all accessories and colored for the 2 units concrete counter finished with granite slab.
  - b. Provide storm drainage system for the whole building (Grids 1 & 6). Downspouts should be installed for every column.

*Note: For grid 1, connect the downspout from the gutter to the existing downspout at fourth floor.*

**GENERAL NOTES:**

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities (BOQ) but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop (envelop 2).*
2. The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Further, consult the plan and the scope of works as well as the end-user and inspector for the extent of tasks of the contract.
3. In the event that discrepancies on plans and scope of work occurs, generally, the scope of works prevails. Further, whichever is advantageous to the government is given priority.



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph


4. For concrete works: provide ready mixed concrete of specified strength.
5. Materials to be used on site must be subjected to material testing which will be charged to the contractor.
6. Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy-duty lever type.
7. Multi-roles are allowed for the key personnel who are the engineers and managers of the project.
8. All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.


Prepared by:


  
**EFREN R. ROCILLO**  
TWG Chair


  
**CENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member


  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

  
**TRISHA MARIE I. JULIANO**  
TWG Member

  
**RYAN JANSSEN R. SANCHEZ**  
TWG Member

Approved by:

  
**MA. AGNES P. NUESTRO, Ph.D.**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_