



BILL OF QUANTITIES

NAME OF PROJECT: REPAINTING OF UNIVERSITY LIBRARY			Bill of Quantities		
ABC: ₱ 1,839,481.22					
COLLEGE/UNIT/CAMPUS: MAIN CAMPUS					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	Scrapping Works (Pesos _____ _____ and _____ centavos)				
II	Ceiling Works (Pesos _____ _____ and _____ centavos)				
III	Painting Works (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words		_____ _____ _____			

Submitted by: _____ Date: _____
 Name of Bidder/Bidder's Representative: _____
 (Signature over Printed Name)
 Position: _____
 Construction Company/Contractor: _____

CAVITE STATE UNIVERSITY

SCOPE OF WORKS:

A. REPAINTING OF UNIVERSITY LIBRARY

1. The project should be finished for 60 calendar days.
2. Actual site inspection is a must to verify existing structure.
3. The area should be cleared/cleaned before and after the construction work. Unusable used formworks, excessive soil fill and all other unwanted debris of construction works should be disposed properly.
4. Cleaning up of site, clearing, hauling and disposal of waste and construction debris. Restoration of any damages shall also be done before exiting the area.

I. Painting Works

1. Repainting of the whole exterior portion of the building, ceiling eave and roofing including door and steel casement window and its grills.
 - Scrape old paints and clean all surfaces.
 - Repair surface imperfections with suitable putty.
 - Apply flat latex paint and finished with a minimum of two coat of semi-gloss dirt resisting paint for concrete.
 - Apply rust remover for roofing and steel casement windows/grills.
 - Apply a minimum of two coats of semi-gloss QDE for steel and woods.
 - Apply a minimum of two coats of roofing paint (Baguio green) to the entire roofing of eaves/canopy and ground floor lobby.
 - Apply paints by brush or roller
2. Repair and Improvement of all ceiling eaves (pre-painted spandrel)
 - Provide end/center molding and additional rivets and replacement of dilapidated pre-painted spandrel and furring.
3. Formworks/scaffolding needed shall be provided by the contractor.
4. Clean/clear all areas affected by the works.
5. **Consult the inspector, unit-in-charge / end user for further extent of works**

Note: Color of paint will depend upon the preference of the end-user. Paints and its accessories should be BOYSEN or approved equal.

- A. For color/types of any fixtures or materials to be used on site, consult the end-user and the inspector for approval. Consult the plan and the scope of work for the extent of tasks of the contract. If possible, let the end-user sign your sample as proof of approval.
- B. The plans, detailed drawings and these specifications shall be considered as complementing each other, so that what is mentioned or shown in one, although not mentioned or shown in the other, shall be considered as appearing on both. **In case of conflict between the two, generally, the scope of work prevails.**
- C. Resident site engineer is a must for the projects to be undertaken by the contractor of the university. Safety engineer is a must as per DOLE requirement. **Note: All key personnel should be included in the list of personnel for submission.**
- D. In cases of participation in two or more projects, the set of workers and foreman shall be different per project, however, the set of engineers and equipment may be reused.
- E. Construction safety and health program as well as construction schedule (PERT/CPM/S-Curve) shall be provided by the winning bidder.
- F. All public utilities used by the winning contractor in the construction of the project, such as electricity, water, telephone, etc., shall be for the sole account of the contractor.
- G. See plans/consult the end-user and project inspector for details and extent of work. The silence of specifications, plans, special provisions and supplementary specifications as to any detail, or the apparent omission therein of detailed description or definition of the quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first-class quality are to be used or employed.