



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)

SUPPLEMENTAL / BID BULLETIN NO. 1

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repainting of University Library (CvSU-BAC-INFRA-24-019)** with an **ABC** of **₱ 1,839,481.22**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. The scope of works as rearranged to follow the BOQ and to facilitate estimate preparations.
 - I. Scraping Works
 - a. For concrete/masonry surfaces, scrape old paints. Remove all loose, scaling, flaking and feeling off paints. Paint/varnish remover may be used. Let dry.
 - b. For corroded steel surfaces (roofing and steel casement windows), remove rust by wire brushing and use rust remover/metal etching solution. Let it stay for 15 minutes. Wash off surfaces with water or paint thinner. Let dry.
 - II. Ceiling Works
 - a. Repair and improvement of all ceiling eaves (pre-painted spandrel).
 - a.1 Supply and installation of new end and center moldings.
 - a.2 Replace dilapidated pre-painted spandrel and furring.
 - a.3 Provide additional rivets and needed fastening to repair the ceiling eaves.
 - b. Provide all the formworks and scaffolding needed to complete the project.
 - III. Painting Works

Repainting of the whole exterior portion of the building, ceiling eave and roofing including doors and steel casement windows and its grills. Paint colors should be consulted to the end-user and should be factory mixed.

 - a. After cleaning, repair surface imperfections with suitable putty.
 - b. For concrete: Apply flat latex paint as primer finished with a minimum of 2 coats of semi-gloss dirt resisting paint for concrete.
 - c. For the entire roofing of eaves of canopy and ground floor lobby: Apply a minimum of two coats of roofing paint (baguio green).
 - d. For steel works and wood: Apply primer for steel and for wood, then finish with a minimum of 2 coats of semi-gloss QDE.
4. Clean and clear all areas affected by the works.

GENERAL NOTES:

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities (BOQ) but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop (envelope 2).*
2. *The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector*



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

sign the approved sample. Further, consult the plan and the scope of works as well as the end-user and inspector for the extent of tasks of the contract.

3. *In the event that discrepancies on plans and scope of work occurs, generally, the scope of works prevails. Further, whichever is advantageous to the government is given priority.*
4. *For concrete works: provide ready mixed concrete of specified strength.*
5. *Materials to be used on site must be subjected to material testing which will be charged to the contractor.*
6. *Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy-duty lever type.*
7. *Multi-roles are allowed for the key personnel who are the engineers and managers of the project.*
8. *All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.*
9. *Location of temporary warehouse and barracks will be discussed during the pre-construction meeting.*
10. *All pages of the bidding documents should be originally signed by the authorized signatory (Original, Copy 1 and Copy 2).*
11. *Use readable font size on the detailed estimate.*

SUBMISSION AND OPENING OF BIDS

| | |
|---------------------------|---|
| SUBMISSION OF BIDS | August 15, 2024; 9:00 AM Procurement Office, Administration Building, Cavite State University, Indang, Cavite |
| OPENING OF BIDS | August 15, 2024 S.L. Lasap Hall, Cavite State University, Indang, Cavite 10:00 am – Repainting of University Library 10:30 am – Improvement of Food Processing Building 11:00 am – Repair and Improvement of White House (Converted to Center for Population and Public Health under the College of Medicine 1:00 pm – Improvement of Electrical Power System of CEMDS New and Old Building 1:30 pm – Rehabilitation of Concrete Bridge near NCRDEC and Pink Dormitory 2:00 pm – Improvement of Electrical Power System of Five-Storey Academic Building at CvSU Bacoor Campus |



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

Prepared by:



MICHELLE A. SANTOS
BAC Secretary


EFREN R. ROCILLO
TWG Chair


CENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member


RONALD P. PEÑA
TWG Member


ELPIDIO N. RODEROS, JR.
TWG Member


RYAN JANSSEN R. SANCHEZ
TWG Member

Approved by:


MA. AGNES P. NUESTRO, PhD
Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____