



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite  
www.cvsu.edu.ph

**BIDS AND AWARDS COMMITTEE**  
(INFRASTRUCTURE PROJECTS)

**SUPPLEMENTAL / BID BULLETIN NO. 1**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Repair and Improvement of White House (Converted to Center for Population and Public Health under the College of Medicine) (CvSU-BAC-INFRA-24-021)** with an ABC of **₱ 2,788,569.49**:

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. Earthworks are not included in the scope of work. For item no. II, it should be Masonry and Tile Works. Item III, Carpentry Works. Item IV, Steel Works. Item V, Miscellaneous Works. Item VI, Electrical Works. Item VII, Plumbing Works, and Item VIII, Painting Works. The details and specifications for each item remain unchanged and are included in the scope of work.
4. On Carpentry Works it includes:
  - A. This works consist of restoration of the whole dismantled ceiling area in the ground floor excluding the slab portion of the ceiling.
5. On Steel Works it includes:
  - A. Fabricated Steel Trellis
    - Use 2.00 x 2" x 6" and 2.00 x 2" x 4" galvanized tubular for the fabricated steel trellis frame with polycarbonate twin wall sheets for roofing. (See plans for details)
  - B. Pratt Truss
    - For the pratt truss to support the existing wooden joist:  
Use 2- 1/4" x 2" x 2" angle bar for the top & bottom chord and 1/4" x 1 1/2" x 1 1/2" angle bar for the web member.
6. On Plumbing Works, 2.a, It should be supply and installation of single compartment stainless 304 kitchen sink. Disregard the 3 compartment stainless 304 kitchen sink with food operated faucet complete with accessories.
7. On Plumbing Works, item 9, the construction of the septic tank is also not included in the scope of work.

**GENERAL NOTES:**

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities (BOQ) but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelop (envelope 2).*
2. *The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Further, consult the plan and the scope of works as well as the end-user and inspector for the extent of tasks of the contract.*
3. *In the event that discrepancies on plans and scope of work occurs, generally, the scope of works prevails. Further, whichever is advantageous to the government is given priority.*
4. *For concrete works: provide ready mixed concrete of specified strength.*
5. *Materials to be used on site must be subjected to material testing which will be charged to the contractor.*
6. *Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy-duty lever type.*
7. *Multi-roles are allowed for the key personnel who are the engineers and managers of the project.*
8. *All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.*



9. Location of temporary warehouse and barracks will be discussed during the pre-construction meeting.
10. All pages of the bidding documents should be originally signed by the authorized signatory (Original, Copy 1 and Copy 2).
11. Use readable font size on the detailed estimate.

### SUBMISSION AND OPENING OF BIDS

<b>SUBMISSION OF BIDS</b>	<b>August 15, 2024; 9:00 AM</b> Procurement Office, Administration Building, Cavite State University, Indang, Cavite
<b>OPENING OF BIDS</b>	<b>August 15, 2024</b> S.L. Lasap Hall, Cavite State University, Indang, Cavite  10:00 am – Repainting of University Library  10:30 am – Improvement of Food Processing Building  11:00 am – Repair and Improvement of White House (Converted to Center for Population and Public Health under the College of Medicine  1:00 pm – Improvement of Electrical Power System of CEMDS New and Old Building  1:30 pm – Rehabilitation of Concrete Bridge near NCRDEC and Pink Dormitory  2:00 pm – Improvement of Electrical Power System of Five-Storey Academic Building at CvsU Bacoor Campus

Prepared by:

  
**MICHELLE A. SANTOS**  
BAC Secretary

  
**EFREN R. ROCILLO**  
TWG Chair

  
**CENE M. BAGO**  
TWG Member

  
**LARRY E. ROCELA**  
TWG Member

  
**RONALD P. PEÑA**  
TWG Member

  
**ELPIDIO N. RODEROS, JR.**  
TWG Member

  
**RYAN JANSSEN R. SANCHEZ**  
TWG Member

Approved by:

  
**MA. AGNES P. NUESTRO, PhD**  
Chair, BAC for Infrastructure Projects

Received by the Bidder : \_\_\_\_\_  
Date : \_\_\_\_\_