SUPPLY, DELIVERY AND INSTALLATION OF VARIOUS OFFICE EQUIPMENT FOR THE UNIVERSITY – EARLY PROCUREMENT

LOT B

www.cvsu.edu.ph

ABC: ₱2,950,000.00/ F101

Item No.	Unit	Specifications	Unit Price	Total Price
8	11 Units	AIR CONDITIONING UNIT, 2HP, Window Type Inverter (1 CAS, 1 BRITE, 6 CEMDS, 1 ICTO, 2 Research Lab) - 2HP - Window Type, - Inverter - Cooling Capacity: 18,900 kJ/hr - Power Supply: 230V/ 1Ph/ 60Hz - Remote Controlled - With PS or ICC mark - Warranty: One (1) year on Parts & labor/service	55,000	605,000
9	2 Units	Five (5) years on compressor AIR CONDITIONING UNIT, 4HP, Floor Mounterd,	150,000	300,000
		Inverter, Split Type (CAS) - Installation included with 40AT, 2P, 230V-Circuit Breaker - 4HP - Floor-Mounted, Split Type - Inverter - Cooling Capacity: 39,035 kJ/hr - Power Supply: 230V/ 1Ph/ 60Hz - Remote Controlled - With PS or ICC mark - Warranty: One (1) year on Parts & Labor/service Five (5) years on compressor		
10	10 Units	Aircooler (CED) - For at least 50 sq.m. area - 180watts power - 3-speed powerful airflow 6000m3/h - With three sides cooling pad - 40 ltrs water tank capacity - With timer - With remote controller - Floor standing with castor wheels - Standard Warranty	54,000	540,000
11	1 Unit	AIR CONDITIONING UNIT, 1.5HP, Wall Mounted, Inverter, Split Type (CAS)	55,000	55,000

Item No.	Unit	Specifications	Unit Price	Total Price
		 Installation included with 30AT, 2P, 230V-Circuit Breaker 1.5HP Wall-Mounted, Split Type Inverter Cooling Capacity: 12,000 kJ/hr Power Supply: 230V/ 1Ph/ 60Hz Remote Controlled With PS or ICC mark Warranty: One(1) year on Parts & labor/service Five(5) years on compressor 		
12	1 Unit	AIR CONDITIONING UNIT, 2HP, Wall Mounted, Inverter, Split Type (CAS) - Installation included with 30AT, 2P, 230V-Circuit Breaker - 2HP - Wall-Mounted, Split Type - Inverter - Cooling Capacity:18,900 Kj/hr - Power Supply: 230V/ 1PH/ 60Hz - Remote Controlled - With PS or ICC mark - Warranty: One(1) year on Parts & labor/service Five(5) years on compressor	60,000	60,000
13	10 Units	SPLIT TYPE AIRCONDITIONING UNIT, 3HP (9 CAFENR, 1 BAC) - Installation included - Wall mounted - Inverter with 40AT, 2P, 230V Circuit Breaker - Cooling Capacity: 28,500 kj/hr Warranty: One(1) year on Parts & labor/service Five(5) years on compressor	139,000	1,390,000
	1		TOTAL:	₱2,950,000.00