



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
 Indang, Cavite, Philippines
 ☎ (046) 889-6373
www.cvsu.edu.ph

INVITATION TO SUBMIT QUOTATION
Labor for Repair and Improvement of Comfort Rooms and Roofing of Drawing Room at Engineering Science Building (By Administration)

- The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project **“Labor for Repair and Improvement of Comfort Rooms and Roofing of Drawing Room at Engineering Science Building (By Admin – Pakyaw Labor Group)”** with an Approved Budget for the Contract (ABC) of **Four Hundred Fifty-Five Thousand One Hundred Sixty-Two Pesos and 70/100 Only (PhP 455,162.70)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.	1	Lot	Repair and Improvement of Comfort Rooms and Roofing of Drawing Room at Engineering Science Building (By Admin – Pakyaw Labor Group) • Scope of Work a. Dismantling b. Tile Works c. Roofing Works d. Carpentry Works e. Miscellaneous Works f. Painting Works g. Electrical Works h. Plumbing Works	455,162.70	455,162.70
			(See attached Bill of Quantities)		
TOTAL AMOUNT					455,162.70

- Delivery Period: ____ calendar days from the receipt of P.O.
- Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
- Warranty shall be for a period of six (6) months for supplies and materials. Warranty for equipment must not be less than one (1) year from the date of acceptance and shall be accompanied with Warranty Certificate.
- The quotation must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of December 9, 2024.**

Address : Procurement Office, Administration Building
 Cavite State University
 Indang, Cavite

E-mail : procurementoffice@cvsu.edu.ph/rfqmain@cvsu.edu.ph
Telefax : (046) 889-6373

6. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


ROSELYN M. MARANAN
BAC Secretary, Goods and Consulting Services



BILL OF QUANTITIES

NAME OF PROJECT: LABOR FOR REPAIR AND IMPROVEMENT OF COMFORT ROOMS AND ROOFING OF DRAWING ROOM AT ENGINEERING SCIENCE BUILDING					
ABC: ₱ 455,162.70				Bill of Quantities	
COLLEGE/UNIT/CAMPUS: MAIN CAMPUS					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	DISMANTLING WORKS (Pesos _____ _____ and _____ centavos)				
II	TILE WORKS (Pesos _____ _____ and _____ centavos)				
III	ROOFING WORKS (Pesos _____ _____ and _____ centavos)				
IV	CARPENTRY WORKS (Pesos _____ _____ and _____ centavos)				
V	MISCELLANEOUS WORKS (Pesos _____ _____ and _____ centavos)				
VI	PAINTING WORKS (Pesos _____ _____ and _____ centavos)				
VII	ELECTRICAL WORKS (Pesos _____ _____ and _____ centavos)				
VIII	PLUMBING WORKS (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____

Write grand total in words _____

Submitted by: _____ Date: _____

Name of Bidder/Bidder's Representative: _____

Position: _____

Construction Company/Contractor: _____

SCOPE OF WORKS:

A. REPAIR AND IMPROVEMENT OF COMFORT ROOMS AND ROOFING OF DRAWING ROOM AT ENGINEERING SCIENCE BUILDING

1. The project should be finished for 60 calendar days.
2. Actual Site Inspection is a must.
3. The area should be cleared/cleaned before and after the construction work. Unusable used Formworks, excessive soil fill, and all other unwanted debris of construction should be disposed properly.
4. This set of specification shall govern the methods of construction and the kinds of materials to be used to proposed project shown on the plans and detailed drawings.
5. The plans, detailed drawings and these specifications shall be considered as complementing each other, so that what is mentioned or shown in one, although not mentioned or shown in other shall be considered as appearing on both. In case of conflict between the two, the same should be referred to the project inspector for resolution.
6. All parts of the construction shall be finished with first class workmanship, to the fullest talent and meaning of the plans and these specifications, and the entire satisfaction of the project inspector and the end-user.

B. TECHNICAL DESCRIPTION

I. Dismantling Works

1. The works involve chipping of tiles at comfort rooms (Ground Floor and Second Floor) and dismantling of ceiling at comfort rooms (Ground Floor to Fourth Floor) and dismantling of existing roof at drawing room.
2. Excess materials will be hauled and disposed from the site.

II. Tile Works

1. Supply and Installation of the following:
 - a. Unglazed floor tiles at comfort rooms (Ground Floor to Second Floor) and repair of countertop at Fourth Floor.
 - b. For the comfort room:
 1. Unglazed colored tiles 300mm x 300mm for the flooring.
 2. Glazed colored tiles, 300mm x 300mm for the repair of countertop.
 - c. Consult the end-user for color preference of tiles.

III. Roofing Works

1. Use Pre-Fabricated Rib Type, 0.5mm thick G.I. Sheet
2. Use Teck screw for installation of Roofing.
3. Provide water sealant for all attachment (water sealant should be provided for both inside and outside surface of Teck screw head.

IV. Carpentry Works

1. Provide necessary form lumber and scaffolding needed for the completion of the project.
2. Provide ceiling works for the whole area of comfort rooms from ground floor to fourth floor and drawing rooms.
 - a. Use Fiber Cement Board, 4'x8'x6mm thick.
 - b. Use Metal Furring, 14mm x 50mm x5m x0.5mm
 - c. Use Carrying Channel, 12mm x 35mm x 5m x 0.5mm
 - d. Provide Wall Angle, 40mm x 25mm x 3m x 0.5mm

V01-2018-06-14

- e. Provide Wire Clip, Teck screw, blind rivets and mesh tape for installation of Ceiling.
- f. Provide decorative wooden molding to all ceiling perimeter and corners. Use 1.5" x 1.5" x 8.

V. Miscellaneous Works

Supply and Installation of the following:

1. Doors
12.0 sets D-1 0.70m x 2.10m, Decorative Stainless-Steel Door with complete accessories.
2. Windows
Repair of defective sliding window glass
7.0 sets W-1 0.80m x 1.20m, Glass Window with complete accessories.
3. PVC Partition Wall
Repair of Defective PVC Partition wall of comfort rooms (Ground Floor to Fourth Floor)
4. Others
Installation of 4 sets of stainless grab bar at PWD.

VI. Painting Works

Waterproofing of comfort rooms slab.

1. Surface should be clean, dry, free from oil, grease, dust, dirt, loose materials and other contaminant.
2. Remove dirt, dust, loose or excess grit or mortar with stiff brush and clean surface by high pressure water hosing.
3. The loosening of fallen of concrete have to be removed and the large holes, cracks should be repaired first.
4. All structural cracks must be repaired prior to waterproofing application. Use the required sealants and structural bonding agents.

Painting of Ceiling

1. Apply latex flat as primer. Repair minor surface imperfections with a suitable putty. Let dry, then sand.
2. Apply at least two coats of colored dirt resisting semi-gloss latex paint.
Note: Color of paint will depend upon the reference of the end-user. Paint and its accessories should be BOYSED or approved equal.

VII. Electrical Works

1. All existing lighting fixtures, switches, and outlets at comfort rooms (Ground Floor to Fourth Floor) will be replaced.
2. Installation of lighting fixtures.
 - Installation of 45 sets of 1.20m fluorescent lamp with complete accessories and lower case.
 - Installation of 16 sets of switches and 12 sets of convenience outlet at comfort rooms (Ground to Fourth Floor).
3. Consult plan and inspectors for details and extent of work.

VIII. Plumbing Works

1. Installation of Water Pump
 - Provide 2.5 HP water pump.
2. Installation of Plumbing Fixtures.
 - Provide 10 sets wall hung urinals with complete accessories.
 - Provide 25 sets water closet with complete accessories.
 - Provide 26 pcs floor drains, 12 sets faucets, and 9 sets of lavatories.
3. This work involves repair, / rehabilitation/improvement/declogging of water supply line and sewer line.
4. The work includes cleaning of existing plumbing fixtures that will not be replaced to make them functional.

See plans/consult the end-user and project inspector for details and extent of work. The silence specification, plans, special provisions and supplementary specifications as to any detail, or the apparent omission therein of detailed description or definition of quality of materials and workmanship shall be regarded to mean that only materials and workmanship of first class are to be used or employed.