



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite, Philippines
☎ (046) 889-6373
www.cvsu.edu.ph

INVITATION TO SUBMIT QUOTATION
Repair and Improvement of Cavite City Campus (Straight Contract)

1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project "**Repair and Improvement of Cavite City Campus (Straight Contract)**" with an Approved Budget for the Contract (ABC) **Three Hundred Thirty-Nine Thousand One Hundred Two Pesos only and 98/100 (Php 339,102.98)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.	1	Lot	Repair and Improvement of Cavite City Campus (Straight Contract)	339,102.98	339,102.98
			(See attached Bill of Quantities)		
TOTAL AMOUNT					339,102.98

2. Contract duration: **45** calendar days from the receipt of contract.
3. Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
4. The offer must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of January 16, 2025**.

Address : Procurement Office, Administration Building
Cavite State University
Indang, Cavite

E-mail : svpinframain@cvsu.edu.ph

Telefax : (046) 889-6373
5. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


MICHELLE A. SANTOS
BAC Secretary, Infrastructure Projects



Republic of the Philippines
CAVITE STATE UNIVERSITY
 Don Severino Delas Alas Campus
 Indang, Cavite

BILL OF QUANTITIES

NAME OF PROJECT: REPAIR AND IMPROVEMENT OF CAVITE CITY CAMPUS (BY STRAIGHT CONTRACT)					
ABC: ₱ 399,102.98				Bill of Quantities	
COLLEGE/UNIT/CAMPUS: CvSU CAVITE CITY CAMPUS					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	Dismantling Works (Pesos _____ _____ and _____ centavos)				
II	Concrete, Masonry and Tile Works (Pesos _____ _____ and _____ centavos)				
III	Carpentry Works (Pesos _____ _____ and _____ centavos)				
IV	Miscellaneous Works (Pesos _____ _____ and _____ centavos)				
GRAND TOTAL					_____
Write grand total in words			_____ _____ _____		

Submitted by: _____ Date: _____

Name of Bidder/Bidder's Representative: _____
 (Signature over Printed Name)

Position: _____

Construction Company/Contractor: _____

SCOPE OF WORKS:

A. REPAIR AND IMPROVEMENT OF CAVITE CITY CAMPUS

1. The project should be finished for 45 calendar days.
2. Actual site inspection is a must.
3. The area should be cleared/cleaned before and after the construction work. Unusable used formworks, excessive soil fill and all other unwanted debris of construction works should be disposed properly.

B. TECHNICAL DESCRIPTION

I. DISMANTLING WORKS

1. This works includes dismantling of existing laboratory tables and preparation of PWD Ramp (see plan).

II. CONCRETE, MASONRY AND TILE WORKS

1. Concreting of PWD Ramp with tiles (see plan).
2. Strength of concrete to be adopted shall be 3,000 psi.
3. Provide concrete topping for the canopy/ledge et al chabacano extension (grid D to E/6 to 7)
4. Provide necessary tools and equipment needed for concrete & masonry works.

III. CARPENTRY WORKS

1. Construction of partition at proposed office supply and stock room.
 - Provide good lumber with double wall partition with 1/4 " thk cement board.
2. Provide necessary form lumber and scaffolding needed for the completion of the project.

IV. MISCELLANEOUS WORKS

Supply and Installation of the following

1. Two sets of swing type wooden flush door with jamb at proposed office supply and stock room; complete with all accessories and heavy duty lever type door knob (2.10 m x 1.60m)
2. One set of fixed type window on white powder coated aluminum frame with 1/4" thk. Colored glass; complete with all accessories (1.20 m x 3.0 m)
3. Repair of existing aluminum broken windows at proposed office supply and stock room (Chem Lab Room)
4. Stainless tubing 1" & 2" (304) stainless grills for PWD Ramp (see plan)
5. Stainless sheets (0.4) for the canopy/ledge at el chabacano extension (grid D to E/6 to 7)
6. Reinstallation of aircon condenser at canopy/ledge of el chabacano extension (grid D to E/6 to 7).
7. See plans/consult the end-user and project inspector for details and extent of work.