



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
Don Severino de las Alas Campus  
Indang, Cavite, Philippines  
☎ (046) 889-6373  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**INVITATION TO SUBMIT QUOTATION**  
**Repair and Improvement of IH-1 3<sup>rd</sup> Floor Comfort Rooms (Straight Contract)**

1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project "**Repair and Improvement of IH-1 3<sup>rd</sup> Floor Comfort Rooms (Straight Contract)**" with an Approved Budget for the Contract (ABC) **Five Hundred Twenty-Seven Thousand Eight Hundred Eleven Pesos only and 05/100 (PhP 527,811.05)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.	1	Lot	Repair and Improvement of IH-1 3 <sup>rd</sup> Floor Comfort Rooms (Straight Contract)	527,811.05	527,811.05
			(See attached Bill of Quantities)		
<b>TOTAL AMOUNT</b>					527,811.05

2. Contract duration: **60** calendar days from the receipt of contract.
3. Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
4. The offer must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of January 14, 2025**.

Address : Procurement Office, Administration Building  
Cavite State University  
Indang, Cavite  
E-mail : [svpinframain@cvsu.edu.ph](mailto:svpinframain@cvsu.edu.ph)  
Telefax : (046) 889-6373

5. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.

  
**MICHELLE A. SANTOS**  
BAC Secretary, Infrastructure Projects



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino Delas Alas Campus  
 Indang, Cavite

### BILL OF QUANTITIES

NAME OF PROJECT: REPAIR AND IMPROVEMENT OF IH-1 3 <sup>RD</sup> FLOOR COMFORT ROOMS (BY STRAIGHT CONTRACT) ABC: ₱ 527,811.05 COLLEGE/UNIT/CAMPUS: CvSU INDANG CAMPUS					
Bill of Quantities					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	<b>Dismantling Works</b> (Pesos _____ _____ and _____ centavos)				
II	<b>Carpentry Works</b> (Pesos _____ _____ and _____ centavos)				
III	<b>Miscellaneous Works</b> (Pesos _____ _____ and _____ centavos)				
IV	<b>Electrical Works</b> (Pesos _____ _____ and _____ centavos)				
V	<b>Painting Works</b> (Pesos _____ _____ and _____ centavos)				
VI	<b>Plumbing Works</b> (Pesos _____ _____ and _____ centavos)				
<b>GRAND TOTAL</b>					_____

Write grand total in words \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Submitted by: \_\_\_\_\_ Date: \_\_\_\_\_

Name of Bidder/Bidder's Representative: \_\_\_\_\_  
 (Signature over Printed Name)

Position: \_\_\_\_\_

Construction Company/Contractor: \_\_\_\_\_

**SCOPE OF WORKS:**

**A. REPAIR AND IMPROVEMENT OF IH-1 3<sup>RD</sup> FLOOR COMFORT ROOMS**

1. The project should be finished for **60** calendar days.
2. Actual site inspection is a must.
3. The area should be cleared/cleaned before and after the construction work. Unusable used formworks, excessive soil fill and all other unwanted debris of construction works should be disposed properly.

**B. TECHNICAL DESCRIPTION**

**I. DISMANTLING WORKS**

1. This works includes dismantling of existing ceiling (joist & board), doors, tiles, and plumbing fixture at IH 1 comfort room.
2. The area should be cleared/cleaned before and after the construction works. Unusable used formworks and dismantled materials should be disposed properly.

**II. CARPENTRY WORKS**

1. Provide necessary from lumber and scaffolding needed for the completion of the project.
2. Provide ceiling work for the whole area of the IH 1 Comfort Room.
  - a. Use cement board 3/16" thk for ceiling board
  - b. Use metal furring as ceiling runner/joist and hanger. (Ceiling joist should be installed at 0.40m on center both ways).
  - c. See plan for details.

**III. MISCELLANEOUS WORKS**

**Supply and Installation of the following**

1. Doors
  - 2.0 Set of D-1 wood panel with all accessories.

**IV. TILE WORKS**

1. All tiles for floors shall be finished with 3x3 tiles.
2. The toilet and bathroom floors shall be finished with 3x3 tiles.
3. The walls of the toilets, bathrooms and their adjacent walls should be wainscoted with 3x3 tiles.
4. Interior and Exterior corners of tiled floors and walls shall be provided with the necessary tile mouldings.
5. All tiles for floor, walls and mouldings shall be free from laminatios, serrated edges, chipped-off corners and other defects, which would be adversely affect the appearance and strength. Use tile adhesive for the installation of all tils and mouldings shall be filled with white cement and then carefully wiped.
6. Before the tiles and mouldings are laid in place, they shall be thoroughly soaked in water if recommended by the manufacturer. Mortar to be used in setting the tiles

and mouldings shall be a mixture of 1 part cement and 2 parts sand by volume.

7. Consult the end-user for the color and design preference of the tiles.

**V. PAINTING WORKS**

1. Apply latex flat as primer. Repair minor surface imperfection with skim coat let dry then sand.
2. Apply at least 2 coats of colored semi-gloss latex paint (factory mixed)

**VI. PLUMBING WORKS**

1. Supply of 6 sets of water closet
2. Supply of 6 sets of faucet
3. Supply of 4 set of lavatory

**NOTE: Color of paint will depend upon the preference of the end-user. Paints and its accessories should be BOYSEN or approved equal.**

**See plans/consult the end-user and project inspector for details and extent of work.**