



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
**Don Severino de las Alas Campus**  
Indang, Cavite, Philippines  
☎ (046) 889-6373  
[www.cvsu.edu.ph](http://www.cvsu.edu.ph)

**INVITATION TO SUBMIT QUOTATION**  
**PAINTING OF THREE STOREY MAIN BUILDING FOR NCRDEC (Straight Contract)**

1. The Cavite State University (CvSU) invites interested firms/supplier to submit quotation for the project "**Painting of Three Storey Main Building for NCRDEC (Straight Contract)**" with an Approved Budget for the Contract (ABC) **Six Hundred Sixty-Two Thousand One Hundred Thirty-Seven only and 91/100 (PhP 662,137.91)**. Quotation received in excess of the ABC shall be automatically rejected at the opening.

Item No.	Quantity	Unit	Description	Unit Cost	Total Cost
1.	1	Lot	Painting of Three Storey Main Building for NCRDEC (Straight Contract)	662,137.91	662,137.91
			(See attached Bill of Quantities)		
<b>TOTAL AMOUNT</b>					662,137.91

2. Contract duration: **60** calendar days from the receipt of contract.
3. Price quotations must be valid for a period of sixty (60) calendar days from date of submission and shall include all taxes, duties and/or levies payable. Bidders shall also indicate the brand and model of the items being offered.
4. The offer must be submitted to the Procurement Office through mail, fax or email at the contact details listed below **on or before 5:00 PM of March 24, 2025**.

Address : Procurement Office, Administration Building  
Cavite State University  
Indang, Cavite  
E-mail : [svpinframain@cvsu.edu.ph](mailto:svpinframain@cvsu.edu.ph)  
Telefax : (046) 889-6373

5. The CvSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. CvSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.

  
**MICHELLE A. SANTOS**  
BAC Secretary, Infrastructure Projects



Republic of the Philippines  
**CAVITE STATE UNIVERSITY**  
 Don Severino Delas Alas Campus  
 Indang, Cavite

## BILL OF QUANTITIES

NAME OF PROJECT: PAINTING OF THREE STOREY MAIN BUILDING FOR NCRDEC (BY STRAIGHT CONTRACT) ABC: ₱ 662,137.91 COLLEGE/UNIT/CAMPUS: CvSU INDANG CAMPUS					
<b>Bill of Quantities</b>					
Item No.	Description	Unit	Quantity	Unit Price (Pesos)	Amount (Pesos)
I	<b>Preparation Works</b> (Pesos _____ _____ and _____ centavos)				
II	<b>Scaffolding and Miscellaneous Works</b> (Pesos _____ _____ and _____ centavos)				
III	<b>Painting Works</b> (Pesos _____ _____ and _____ centavos)				
<b>GRAND TOTAL</b>					_____
<b>Write grand total in words</b>			_____ _____ _____		

Submitted by: \_\_\_\_\_ Date: \_\_\_\_\_

Name of Bidder/Bidder's Representative: \_\_\_\_\_  
 (Signature over Printed Name)

Position: \_\_\_\_\_

Construction Company/Contractor: \_\_\_\_\_

### SCOPE OF WORKS:

#### A. PAINTING OF THREE STOREY MAIN BUILDING FOR NCRDEC

1. The project must be finished in **60** working days.
2. Actual site inspection is a must.
3. The area should be cleared/cleaned before and after the construction work. Unusable used formworks, excessive soil fill and all other unwanted debris of construction works should be disposed properly.

**B. TECHNICAL DESCRIPTION**

**I. Preparation Works**

A. Mobilization

1. Provide the following:
  - Billboard
  - Bankhouse with office
  - Temporary comfort rooms
  - Site enclosure

**II. Scaffolding and Miscellaneous Works**

1. Provide necessary form lumber and scaffolding needed for the completion of the project.

**III. Painting Works**

The whole building should be painted (both exterior & interior) include claddings.

**WOOD**

1. Apply one coat of flatwall enamel white. Allow to dry overnight
2. Repair minor surface imperfection with glazing putty. Let dry then sand.
3. Apply at least two coats of Quick Dry Enamel in the desired color. Allow an overnight intercoating interval.

**METAL**

1. Apply epoxy primer by brush or spray. Allow to dry for 24 hours. Apply suitable putty on imperfections.
2. Apply at least two coats of Quicky dry enamel in the desired color.

**CONCRETE**

1. Treat the surface with concrete neutralizer. Mix one part with 16 parts waters by volume
2. Apply skim coat as primer. Repair minor surface imperfections with suitable putty. Let dry, then sand.
3. Apply at least two coats of colored dirt resisting semi-gloss latex paint (factory mixed).

**Note: Color of paint will depend upon the preference of the end-user. Paint and its accessories should be Boysen or approved equal.**

- C. See plans/consult the end-user and project inspector for details and extent of work.