



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

BIDS AND AWARDS COMMITTEE
(INFRASTRUCTURE PROJECTS)

SUPPLEMENTAL / BID BULLETIN NO. 2

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents. Please take note of the changes/adjustments for the project, **Construction of Faculty Housing (Phase II) (CvSU-BAC-INFRA-25-010)** with an **ABC** of **₱ 10,000,000.00**.

1. Site inspection is a must. Verify actual condition of site.
2. Site temporary enclosure may be sack or any suitable materials that may enclose the workplace.
3. For Site Clearing, cutting of trees and clearing works are included. Processing of permit of cutting of trees will be shouldered by the University. Processing of building permit, and all other related permits should be shouldered by the contractor.
4. For Miscellaneous Works, all windows should have ¼" thick colored glass on powder coated finish on aluminum frame.
5. Toilet and bath do not need for waterproofing.
6. 3 bore holes for soil boring test.
7. For floor finishes, see Item IV (Tile Works) in the scope of work.
8. For wall finishes, see Item III (Masonry Works) in the scope of work.
9. For ceiling finishes, see Item V.B. (Carpentry Works – Ceiling Works).
10. For Masonry Works, include the construction of retaining wall with total length of 65.0 meters. See Bid Bulletin Plan 01.
11. For items including the mobilization, demobilization and processing of permits, required to provide a detailed breakdown of costs. These items should not be presented as lump sum amounts, but rather as itemized cost components.
12. Detailed Cost Estimate will be provided by the contractor using their own format.
13. For the location of exhaust fan and emergency light, see additional plan E-1.
14. For the location of service entrance concrete pedestal, see additional plan E-3
15. There are revisions in the single line diagram of electrical works, see revised plan E-2.
16. Four sets of duplex houses shall be constructed as per the approved plans.
17. Registered Electrical Engineer (REE) is required for the supervision of the work, and a Professional Electrical Engineer (PEE) is required for the signing and sealing of the test results for electrical components, as well as the Final Electrical Inspection Report (with notary public) to be submitted during the Final Billing. The PEE may be a consultant; a notarized contract should be included in the bid to be submitted.

GENERAL NOTES:

1. *This bid bulletin does not cancel the information given in the scope of work of the Bill of Quantities (BOQ) but adds clarification to it. Please attach this added information/bid bulletin to the BOQ and include in the financial envelope (envelope 2).*
2. *The colors, types and specifications of all fixtures and materials to be used on site should be consulted to the inspector or end-user for approval. As possible, let the end-user or the inspector sign the approved sample. Further, consult the plan and the scope of works as well as the end-user and inspector for the extent of tasks of the contract.*
3. *In the event that discrepancies on plans and scope of work occurs, generally, the scope of works prevails. Further, whichever is advantageous to the government is given priority.*
4. *For concrete works: provide ready mixed concrete of specified strength.*



Republic of the Philippines
CAVITE STATE UNIVERSITY
Don Severino de las Alas Campus
Indang, Cavite
www.cvsu.edu.ph

5. *Materials to be used on site must be subjected to material testing which will be charged to the contractor.*
6. *Let it be observed that all door knobs to be installed on doors of all buildings be that of heavy-duty lever type.*
7. *Multi-roles are allowed for the key personnel who are the engineers and managers of the project.*
8. *All certifications and pertinent documents on electrical works shall be signed and sealed by PEE. In addition, electrical permits shall be up to securing approved CFEI.*
9. *Location of temporary warehouse and barracks will be discussed during the pre-construction meeting.*
10. *All pages of the bidding documents should be originally signed by the authorized signatory (Original, Copy 1 and Copy 2). The use of the Certified True Copy stamp is not required.*
12. *Use readable font size on the detailed estimate.*


Prepared by:



MICHELLE A. SANTOS
BAC Secretary



EFREN R. ROCILLO
TWG Chair


GENE M. BAGO
TWG Member


LARRY E. ROCELA
TWG Member



RONALD P. PEÑA
TWG Member


ELPIDIO N. RODEROS, JR.
TWG Member


TRISHA MARIE I. JULIANO
TWG Member


RYAN JANSSEN R. SANCHEZ
TWG Member

Approved by:


MELBOURNE R. TALACTAC, PhD
Chair, BAC for Infrastructure Projects

Received by the Bidder : _____
Date : _____